



ERONGO
CONSULTING
GROUP



Environmental and Social Impact Assessment (ESIA) Report

For the Design, Construction, and Operation of a Wastewater Treatment Plant for the New Secondary School at Epembe, Ohangwena Region, Namibia

Prepared by:	Erongo Consulting Group (Pty) Ltd
Reference No:	#250621005958
Date:	June 21, 2025, 09:25 PM CAT
Competent Reviewer:	Environmental Commissioner, Ministry of Environment & Tourism
Proponent:	Ministry of Education, Innovation, Youth, Sports, Arts and Culture



ARTEE PROJECT ENGINEERS



INSTITUTE FOR
IMPACT SCIENCES
& RESEARCH DESIGN

Environmental and Social Impact Assessment (ESIA) Report

For the Design, Construction, and Operation of a Wastewater Treatment Plant for the New Secondary School at Epembe, Ohangwena Region, Namibia

Prepared by:	Erongo Consulting Group (Pty) Ltd
Reference No:	#250621005958
Date:	June 21, 2025, 09:25 PM CAT
Competent Reviewer:	Environmental Commissioner, Ministry of Environment, Forestry and Tourism (MEFT)
Proponent:	Ministry of Education, Innovation, Youth, Sports, Arts and Culture

Document Status

This document represents the **final draft** of the Environmental and Social Impact Assessment (ESIA) for the proposed Epembe Secondary School and Wastewater Treatment Plant (WWTP) project, submitted to the Environmental Commissioner, Ministry of Environment, Forestry and Tourism (MEFT), on June 21, 2025, for review and issuance of the Environmental Clearance Certificate (ECC) as required under the Environmental Management Act (No. 7 of 2007) and its regulations (Government Notice No. 30 of 2012). All stakeholder consultations, including public meetings (Ref: PC-250505), focus group discussions (Ref: FGD-250515), household surveys (Ref: HS-250525), and written submissions (Ref: WS-250601), have been incorporated, and the report has undergone internal quality assurance by **Erongo Consulting Group**, and the **Institute for Impact Sciences & Research Design**, to ensure compliance with national and international standards.

Disclaimer

This Environmental and Social Impact Assessment (ESIA) report has been prepared by Erongo Consulting Group (Pty) Ltd for the Ministry of Education, Innovation, Youth, Sports, Arts and Culture, in accordance with the Environmental Management Act (No. 7 of 2007) and the

Environmental Impact Assessment Regulations (Government Notice No. 30 of 2012) of the Republic of Namibia. The information, data, and recommendations presented herein are based on baseline studies, stakeholder consultations, and technical assessments conducted up to June 21, 2025, and reflect the best available knowledge at the time of submission.

Erongo Consulting Group (Pty) Ltd has exercised due care and diligence in preparing this report but does not warrant the accuracy or completeness of information provided by third parties, including stakeholders, contractors, or public sources. The findings, interpretations, and conclusions expressed in this report are those of the authors and do not necessarily reflect the views of the Ministry of Education, Innovation, Youth, Sports, Arts and Culture, the Ministry of Environment, Forestry and Tourism (MEFT), or any other consulted parties.

This report is intended solely for the purpose of obtaining an Environmental Clearance Certificate (ECC) for the Epembe Secondary School and WWTP project and for use by the project proponent, regulatory authorities, and relevant stakeholders as part of the decision-making process. It is not to be used for any other purpose without prior written consent from Erongo Consulting Group (Pty) Ltd. The report may not be distributed, reproduced, or disclosed to unauthorized parties without express permission, except as required under Namibian law.

Erongo Consulting Group (Pty) Ltd, and the **Institute for Impact Sciences & Research Design**, employees, and its subcontractors shall not be held liable for any direct, indirect, or consequential damages arising from the use, misuse, or reliance on the information contained in this report. Users of this report are responsible for conducting their own due diligence and verifying the applicability of the findings to their specific needs. Any changes in project scope, site conditions, or regulatory requirements after June 21, 2025, may require additional assessments or updates to this ESIA.

Citation

Erongo Consulting Group (Pty) Ltd. (2025). *Environmental and Social Impact Assessment for the Epembe Secondary School and Wastewater Treatment Plant, Ohangwena Region, Namibia*. Reference No: #250621005958. Prepared for the Ministry of Education, Innovation, Youth, Sports, Arts and Culture, Windhoek, Republic of Namibia.

List of Acronyms with Full Forms and Descriptions

Acronym	Full Form	Description
ARIMA	AutoRegressive Integrated Moving Average	A statistical model used for analyzing and forecasting time-series data, applied for predicting environmental recovery trajectories during monitoring.
BOD	Biochemical Oxygen Demand	A measure of oxygen required by aerobic organisms to break down organic material in water; targets BOD <25 mg/L for effluent to protect the oshana.
CAT	Central Africa Time	Time zone (UTC+2) used in Namibia, referenced in the document's preparation timestamp.
CBWC	Cuvelai Basin Water Commission	Manages the Cuvelai Basin ecosystem, including the oshana, involved in stakeholder engagement for water management.
CFU	Colony Forming Units	Estimates viable bacteria or fungal cells; targets E. coli <150 CFU/100 mL in effluent for public health safety.
CRP	Closure and Rehabilitation Plan	Plan for decommissioning the WWTP and restoring the site, targeting >90% vegetation recovery and <5 mg/kg soil contaminants.
DO	Dissolved Oxygen	Oxygen dissolved in water, critical for aquatic life; requires DO >4 mg/L in the oshana to prevent degradation.
EAP	Environmental Assessment Practitioner	Entity (e.g., Erongo Consulting Group) conducting the ESIA, including data collection and stakeholder coordination.
ECC	Environmental Clearance Certificate	Approval issued by MEFT upon ESIA review, required for project commencement.
EMP	Environmental Management Plan	Framework for mitigating and monitoring environmental and social impacts throughout the project lifecycle.
ERT	Emergency Response Team	Multi-stakeholder team for handling incidents like spills, with training and communication protocols.
ESIA	Environmental and Social Impact Assessment	Systematic evaluation of the project's environmental and social impacts, including baseline studies and mitigation plans.
FAO	Food and Agriculture Organization	UN agency; its soil description guidelines inform site characterization (sandy loam, <10% silt).
FGD	Focus Group Discussion	Structured stakeholder discussions; used for community input on oshana impacts (Ref: FGD-250515).
GIS	Geographic Information System	System for spatial data analysis; used for mapping the site and oshana within a 5-km radius.
HDPE	High-Density Polyethylene	Durable plastic for the 200-m WWTP pipeline, with a 50-year design life.
HS	Household Survey	Data collection on community water access and health; referenced in Ref: HS-250525.
I&APs	Interested and Affected Parties	Stakeholders (e.g., residents, organizations) providing input via consultations.
IAIA	International Association for Impact Assessment	Global body; its principles guide the ESIA's participatory and rigorous approach.

ICP-MS	Inductively Coupled Plasma Mass Spectrometry	Technique for detecting metals in soil/water; used to ensure <5 mg/kg contaminants.
IFC	International Finance Corporation	World Bank Group member; its Performance Standards (2012) guide pollution prevention and biodiversity protection.
ISO	International Organization for Standardization	Provides standards for risk management (ISO 31000) and environmental systems (ISO 14001).
MEFT	Ministry of Environment, Forestry and Tourism	Namibia's regulatory authority for ESIA review and compliance (also referred to as MET).
MLSS	Mixed Liquor Suspended Solids	Suspended solids in the activated sludge process; maintained at 2,500–3,500 mg/L in the WWTP.
NQA	Namibia Qualifications Authority	Certifies vocational training for WWTP operators.
PC	Public Consultation	Stakeholder engagement activities; referenced in minutes (Ref: PC-250505).
PM10	Particulate Matter 10 micrometers	Fine airborne particles; monitored to limit dust impacts (<90 µg/m ³) during construction.
SCADA	Supervisory Control and Data Acquisition	System for real-time monitoring of WWTP operations (e.g., pressure, flow).
SDGs	Sustainable Development Goals	UN goals; project aligns with SDG 4 (Quality Education) and SDG 6 (Clean Water and Sanitation).
TSS	Total Suspended Solids	Particles in water; targeted at <20 mg/L in effluent to prevent oshana sedimentation.
WHO	World Health Organization	UN agency; its guidelines inform drinking-water quality and health risk assessments.
WS	Written Submissions	Stakeholder feedback compiled in Ref: WS-250601 during the consultation period.
WWTP	Wastewater Treatment Plant	Facility treating 60–80 m ³ /day of school wastewater using activated sludge and UV disinfection.

Contents

Document Status	2
Disclaimer	2
Citation	3
List of Acronyms with Full Forms and Descriptions	4
Executive Summary	11
1. INTRODUCTION	12
1.1. Project Background	12
1.2. Objectives of the ESIA	13
1.3. Scope and Methodology	13
2. PROJECT DESCRIPTION	17
2.1. Project Rationale and Objectives	17
2.2. Project Location and Site Characteristics	19
2.2.1. Geographical Context	19
2.3. Site Conditions	19
2.3.1. Soil Profile	19
2.3.2. Hydrology	20
2.3.3. Climate	20
2.3.4. Vegetation	20
2.4. Infrastructure Description	21
2.4.1. Wastewater Treatment Plant	21
2.4.2. Pipeline System	21
2.4.3. Power Supply	22
2.4.4. Ancillary Facilities	22
2.5. Civil Engineering Design	22
2.5.1. Foundation and Structural Elements	22
2.5.2. Hydraulic Design	22
2.5.3. Materials Specification	23
2.6. Construction Phases	23
2.6.1. Phase 1: Site Preparation (3 Months)	23
2.6.2. Phase 2: Infrastructure Installation (6 Months)	23
2.6.3. Phase 3: Commissioning (2 Months)	23
2.7. Operation Procedures	24
2.7.1. Wastewater Treatment Process	24

2.7.2.	Staffing and Scheduling	24
2.8.	Maintenance Protocols.....	24
2.8.1.	Routine Maintenance	24
2.8.2.	Preventive Measures	24
2.9.	Project Timeline and Estimated Cost Estimate	25
2.10.	Institutional Responsibilities	25
	References.....	27
3.	POLICY, LEGAL, AND ADMINISTRATIVE FRAMEWORK	28
3.1.	National Legislation	28
3.2.	International Guidelines and Standards	30
3.3.	Institutional Responsibilities	32
	References.....	34
4.	BASELINE ENVIRONMENTAL AND SOCIAL CONDITIONS	35
4.1.	Epembe Site Conditions	35
4.1.1.	Environmental Conditions	35
4.1.2.	Socio-Economic Conditions	37
4.1.3.	Cultural and Historical (Heritage) Conditions	38
4.2.	Ohangwena Region Conditions	39
4.2.1.	Environmental Conditions	39
4.2.2.	Socio-Economic Conditions	41
4.2.3.	Cultural and Historical (Heritage) Conditions	42
5.	IMPACT ASSESSMENT AND MITIGATION MEASURES	43
5.1.	Impact Identification and Assessment.....	43
5.1.1.	Construction Phase Impacts	43
5.1.2.	Operation Phase Impacts	44
5.1.3.	Decommissioning Phase Impacts.....	44
6.	ENVIRONMENTAL MANAGEMENT PLAN (EMP).....	48
6.1.	EMP Matrix	48
6.2.	Supporting Details.....	53
6.2.1.	Institutional Responsibilities	53
6.2.2.	Reporting and Adaptive Management	53
6.2.3.	Budget and Schedule (estimate)	53
7.	STAKEHOLDER ENGAGEMENT AND CONSULTATION	54
7.1.	Objectives and Principles	54
7.2.	Stakeholder Identification and Analysis	54

7.3.	Consultation Process and Methods	54
7.4.	Key Issues and Responses.....	55
7.5.	Ongoing Engagement and Grievance Mechanism	55
7.5.1.	Ongoing Engagement	55
7.5.2.	Grievance Redressal Mechanism	56
7.6.	Integration into Project Design	56
7.7.	Monitoring and Reporting	56
8.	ENVIRONMENTAL AND SOCIAL MONITORING AND EVALUATION	57
8.1.	Objectives and Scope.....	57
8.2.	Monitoring Program	57
8.2.1.	Pre-Construction Monitoring	57
8.2.2.	Construction Monitoring.....	58
8.2.3.	Operation Monitoring	58
8.2.4.	Decommissioning Monitoring	58
8.3.	Evaluation Methodology.....	59
8.4.	Reporting Framework.....	59
8.5.	Institutional Responsibilities	59
8.6.	Adaptive Management.....	59
9.	ALTERNATIVES ANALYSIS	60
9.1.	Methodology.....	60
9.2.	No-Action Alternative	60
9.2.1.	Description	60
9.2.2.	Impacts	60
9.2.3.	Evaluation	61
9.3.	Alternative Treatment Technologies	61
9.3.1.	Constructed Wetlands	61
9.3.2.	Activated Sludge (Proposed)	61
9.3.3.	Membrane Bioreactor (MBR)	61
9.4.	Alternative Site Locations	62
9.4.1.	Site A (Current, East of D3602).....	62
9.4.2.	Site B (1 km West of D3602).....	62
9.5.	Alternative Mitigation Strategies	62
9.5.1.	50-m Vegetated Buffer (Proposed)	62
9.5.2.	100-m Concrete Barrier.....	62
9.6.	Conclusion and Recommendation.....	63

10.	RISK ASSESSMENT AND EMERGENCY PREPAREDNESS	63
10.1.	Risk Assessment Methodology	64
10.2.	Identification and Characterization of Risks	64
10.2.1.	Pre-Construction Risks	64
10.2.2.	Construction Risks	64
10.2.3.	Operation Risks.....	65
10.2.4.	Decommissioning Risks	65
10.4.	Emergency Preparedness Plan	67
10.4.1.	General Preparedness Framework.....	67
10.4.2.	Phase-Specific Emergency Measures	67
10.4.3.	Contingency Resource Allocation	67
10.5.	Risk Mitigation Strategies.....	67
10.6.	Monitoring and Evaluation of Risks	68
10.7.	Institutional Responsibilities	68
11.	CLOSURE AND REHABILITATION PLAN	69
11.1.	Objectives and Scope.....	69
11.2.1.	Infrastructure Dismantling	69
11.2.2.	Waste Management.....	70
11.3.	Rehabilitation Strategy.....	70
11.3.1.	Site Regrading and Stabilization	70
11.3.2.	Vegetation Restoration	70
11.3.3.	Socio-Economic Rehabilitation	71
11.4.	Monitoring and Evaluation	71
11.4.1.	Environmental Monitoring.....	71
11.4.2.	Socio-Economic Monitoring.....	71
11.4.3.	Evaluation Methodology.....	71
11.5.	Reporting and Adaptive Management	71
11.6.	Institutional Responsibilities	72
11.7.	Cost Estimation and Schedule.....	72
12.	CONCLUSION AND RECOMMENDATIONS.....	72
12.1.	Summary of Findings.....	73
12.1.1.	Environmental Impacts	73
12.1.2.	Social and Cultural Impacts.....	73
12.1.3.	Mitigation Effectiveness.....	73
12.2.	Conclusion	73

12.3. Recommendations	74
12.3.1. Pre-Construction Phase	74
12.3.2. Construction Phase	74
12.3.3. Operation Phase	74
12.3.4. Decommissioning and Rehabilitation Phase	75
12.3.5. Institutional and Monitoring Recommendations	75
12.4. Final Remarks	75
13. REFERENCES FOR THE EPEMBE ESIA	76
APPENDICES TABLE OF CONTENTS	79
Appendix 7.3.1: Minutes of Stakeholder Engagement (Ref: PC-250505)	79
Appendix 7.3.2: Focus Group Discussion Report (Ref: FGD-250515)	80
Appendix 7.3.3: Household Survey Report (Ref: HS-250525)	81
Appendix 7.3.4: Written Submissions Report (Ref: WS-250601)	82
Appendix 7.3.5: Media Outreach Report	82
Appendix 7.3.6: Interested and Affected Parties (I&AP) Register	82
Appendix A: Effluent Quality Monitoring Form	86
Appendix B: Sludge Management Monitoring Form	86
Appendix C: Infrastructure Integrity Monitoring Form	87
Appendix D: Energy Consumption Monitoring Form	87
Notes:	87

Executive Summary

This Environmental and Social Impact Assessment (ESIA) report evaluates the environmental and social implications of constructing a new secondary school and an integrated wastewater treatment plant (WWTP) at Epembe, Ohangwena Region, Namibia, commissioned by the Ministry of Education, Innovation, Youth, Sports, Arts and Culture. The project develops a modern educational facility for 600 learners, including hostels and teacher housing, on a 350,000 m² (35-hectare) site east of the D3602 road. The WWTP is designed to treat 60 - 80 m³/day of wastewater, based on a per capita generation rate of 100 - 150 liters/person/day (Metcalf & Eddy, 2014), using a multi-stage process: preliminary screening and grit removal, primary sedimentation (10 m³ tank), secondary activated sludge treatment with a 6 - 8 hour hydraulic retention time and mixed liquor suspended solids (MLSS) of 2,500 - 3,500 mg/L, and tertiary UV disinfection (45 mJ/cm²). This ensures compliance with the Water Resources Management Act (No. 11 of 2013) standards, targeting Biochemical Oxygen Demand (BOD) <25 mg/L and Total Suspended Solids (TSS) <20 mg/L. Treated effluent is discharged into the oshana, a seasonal wetland 300 - 400 m southeast within the Cuvelai Basin, requiring robust environmental safeguards.

The ESIA complies with the Environmental Management Act (No. 7 of 2007) and its Regulations (2012), adhering to the International Association for Impact Assessment (IAIA) Principles (2015) and International Finance Corporation (IFC) Performance Standards (2012). Construction impacts include the loss of 0.5 ha of native vegetation (e.g., *Colophospermum mopane*, *Acacia* spp.), soil erosion on sandy substrates (<5 kPa cohesion), noise up to 80 dB from machinery, and dust affecting air quality within 500 m. Operationally, risks include oshana water quality degradation (e.g., DO <4 mg/L), odour from suboptimal sludge management (15 - 20 m³/month), and soil contamination if sludge is untreated. Decommissioning requires landscape restoration and infrastructure disposal.

Socio-economically, the project offers 20–50 temporary construction jobs and 5 - 10 long-term WWTP maintenance roles, enhancing educational access for Epembe's 1,500 - 2,000 residents under the Ohangwena Regional Council's communal land system. However, it may disrupt grazing, increase traffic risks on D3602, and raise community concerns about the oshana's ecological role in agriculture and livestock.

Baseline data from May - June 2025 surveys depict a semi-arid landscape with 70% savanna-woodland cover, hosting small mammals (e.g., *Lepus capensis*), birds (e.g., *Francolinus* spp.), and reptiles (e.g., *Agama* spp.). The oshana, active November - April with 400 - 600 mm rainfall, supports amphibians and invertebrates. Homesteads 200–300 m northwest rely on subsistence farming.

The ESIA proposes an Environmental Management Plan (EMP) with silt fences, biofilters, and continuous effluent monitoring, plus social initiatives like liaison committees and training. An alternatives analysis favors the activated sludge WWTP east of D3602 with a 50-m vegetated buffer, rejecting no-action and costlier options (e.g., MBR). Stakeholder engagement, concluded June 5, 2025, via meetings and submissions, shaped mitigation. Submitted on June 21, 2025 (Ref No: #250621005958).


1. INTRODUCTION

1.1. Project Background

The Epembe Secondary School project, a flagship initiative of the Ministry of Education, Innovation, Youth, Sports, Arts and Culture, aims to address educational disparities in rural Namibia. Located on a 350,000 m² (35-hectare) parcel of communal land east of the D3602 road in the Ohangwena Region at coordinates 17°47'27"S, 16°27'04"E, the site features deep sandy soils (<10% silt, cohesion <5 kPa) with a 2–5% southwest gradient toward an adjacent oshana. The lack of existing sanitation infrastructure necessitates a wastewater treatment plant (WWTP) to support 600 learners, including hostel facilities and teacher housing, generating an estimated 60 - 80 m³/day of wastewater based on a per capita rate of 100 -150 liters/person/day (Metcalf & Eddy, 2014). The WWTP employs a multi-stage process: preliminary screening with 5 mm bar screens to remove 0.5–1 m³/day of coarse solids, grit chambers for sediment settlement, a 10 m³ primary sedimentation tank reducing 50 - 60% organic load, secondary activated sludge treatment with a mixed liquor suspended solids (MLSS) concentration of 2,500 - 3,500 mg/L and 6 - 8 hour hydraulic retention time, and tertiary UV disinfection (45 mJ/cm²) to achieve <150 CFU/100 mL E. coli (Tchobanoglous et al., 2014). Treated effluent will be discharged into the oshana, a seasonal wetland 300–400 m southeast within the Cuvelai Basin, requiring compliance with the Water Resources Management Act (No. 11 of 2013) standards (BOD <25 mg/L, TSS <20 mg/L).

This project supports Namibia's National Development Plan 5 (2021–2026) and Vision 2030, promoting equitable education and sustainable infrastructure. It addresses public health gaps under the Public and Environmental Health Act (No. 1 of 2015) in a region where only 30% of 1,500–2,000 residents have treated sanitation. The site's proximity to homesteads (200–300 m northwest) and the oshana underscores the need for integrated environmental and social planning, balancing development with the wetland's ecological and cultural significance.

Figure 1: Proposed Epembe Secondary School Site, Ohangwena Region, Namibia, located at coordinates 17°47'27"S, 16°27'04"E, showcasing the 35-hectare development area east of the D3602 road, adjacent to the oshana wetland



1.2. Objectives of the ESIA

The ESIA is designed to provide a scientifically rigorous framework for evaluating the environmental and social consequences of the Epembe project, ensuring compliance with national regulatory frameworks and international best practices. The specific objectives are as follows:

- **Impact Identification and Quantification:** Systematically identify and assess potential adverse effects on the physical environment (e.g., soil erosion, water quality), biological components (e.g., habitat loss, species displacement), and socio-economic fabric (e.g., land use conflicts, employment opportunities) across the project's construction, operation, and decommissioning phases. This process employs a risk-based matrix adapted from Glasson et al. (2012), evaluating impact magnitude, duration, and reversibility.
- **Mitigation and Management Development:** Develop an Environmental Management Plan (EMP) integrating engineering interventions (e.g., erosion control structures, effluent treatment optimization) and social programs (e.g., community capacity building) to mitigate identified impacts, drawing on World Bank Environmental and Social Framework (2017) guidelines.
- **Alternative Evaluation:** Conduct a comparative analysis of feasible alternatives, including the no-project scenario, alternative site locations within the Ohangwena Region, and alternative wastewater treatment technologies (e.g., constructed wetlands, membrane bioreactors), to ascertain the most environmentally and socially sustainable option, consistent with IAIA Principle 6 (2015).
- **Stakeholder Engagement and Integration:** Facilitate participatory processes with Interested and Affected Parties (I&APs), as required by the Environmental Management Act Regulations (2012), to incorporate local knowledge, address grievances, and enhance project acceptance. This includes public consultations initiated with a deadline of 5 June 2025.

The ESIA serves as a decision-support tool, enabling the Ministry of Environment (MET) to issue an Environmental Clearance Certificate based on evidence-based findings.

1.3. Scope and Methodology

The ESIA encompasses a detailed assessment of the 200,000 m² project site and a 5-kilometer radius of influence, situated within a communal land tenure system under the Ohangwena Regional Council. The methodology adheres to a structured, multi-disciplinary approach, as outlined by Glasson et al. (2012), integrating primary data collection, secondary source analysis, and stakeholder input:

- **Baseline Characterization:** Field investigations, conducted from May to June 2025 at coordinates 17°47'00"S, 16°27'00"E, employed transect surveys to document physical parameters (e.g., topography, soil texture), biological attributes (e.g., vegetation cover, faunal diversity), and socio-economic indicators (e.g., population density, land use). Satellite imagery and Geographic Information System (GIS) tools facilitated spatial mapping, identifying homesteads 200–300 meters northwest and the oshana 300–400 meters southeast.
- **Impact Assessment:** Potential impacts were identified through a scoping exercise, with significance evaluated using a weighted criteria matrix (magnitude, duration, frequency, and receptor sensitivity), aligned with IAIA guidelines (2015). Cumulative impact assessment considered regional hydrological and land-use trends within the Cuvelai Basin.
- **Mitigation Planning:** The EMP was developed using a hierarchical approach (avoid, minimize, mitigate, compensate), incorporating engineering solutions (e.g., silt fences, UV disinfection units) and social measures (e.g., employment quotas), informed by the World Bank Environmental and Social Framework (2017).
- **Public Consultation:** A participatory process was initiated with a public notice period ending 5 June 2025, involving community meetings, written submissions, and traditional authority consultations. Feedback was systematically recorded and integrated into the impact assessment, ensuring transparency and accountability.

1.4. Regulatory and Policy Alignment

The Environmental and Social Impact Assessment (ESIA) for the Epembe Secondary School and Wastewater Treatment Plant (WWTP) project is anchored in a robust framework of national legislation and international standards, ensuring a legally compliant and environmentally sustainable development process. At the national level, the ESIA adheres to the **Environmental Management Act (No. 7 of 2007)** and its associated **Environmental Impact Assessment Regulations (Government Notice No. 30 of 2012)**, which mandate a comprehensive assessment of projects with potential significant environmental impacts, such as wastewater discharge into the oshana. This legislation requires the identification of baseline conditions, impact prediction, and the development of mitigation measures, forming the cornerstone of the current assessment.

The **Water Resources Management Act (No. 11 of 2013)** provides regulatory oversight for effluent quality, stipulating discharge limits (e.g., Biochemical Oxygen Demand [BOD] <30 mg/L, Total Suspended Solids [TSS] <25 mg/L) to protect the Cuvelai Basin's hydrological integrity, a critical consideration given the oshana's role as a receiving environment. Additionally, the **Public and Environmental Health Act (No. 1 of 2015)** imposes obligations to safeguard public health by preventing contamination from untreated wastewater, a pertinent concern for the rural community of Epembe, where homesteads are located 200–300 meters northwest of the 350,000 m² site.

Complementing these national statutes, the ESIA aligns with international guidelines to enhance its global relevance and credibility. The **International Association for Impact Assessment (IAIA) Principles of Environmental Impact Assessment Best Practice (2015)** emphasize a participatory, transparent, and scientifically rigorous process, which is reflected in the stakeholder consultation initiated with a deadline of 5 June 2025. The **International Finance Corporation (IFC) Performance Standards (2012)**, particularly Performance Standard 1 (Assessment and Management of Environmental and Social Risks and Impacts) and Performance Standard 3 (Resource Efficiency and Pollution Prevention), guide the assessment of biodiversity impacts on the oshana and the optimization of WWTP design (e.g., activated sludge with a mixed liquor suspended solids [MLSS] concentration of 2,000–3,000 mg/L). Furthermore, the **Ramsar Convention on Wetlands (1971)**, to which Namibia is a signatory, underscores the ecological significance of the oshana as a seasonal wetland habitat, necessitating measures to maintain its biodiversity and hydrological function. The **Equator Principles (2020)**, adopted by financial institutions, reinforce the need for environmental and social risk management, ensuring that the project's financing aligns with sustainable development goals.

This multi-layered regulatory alignment ensures that the ESIA addresses both local contextual needs and global environmental commitments. The integration of these frameworks facilitates a holistic approach, balancing the developmental imperatives of the Ministry of Education, Innovation, Youth, Sports, and Arts and Culture with the conservation priorities of the Ministry of Environment (MET), the designated regulatory authority. The ESIA report, (Reference No: 250621005958), incorporates these standards to support the issuance of an Environmental Clearance Certificate.

1.5. Stakeholder Roles and Responsibilities

The successful execution of the ESIA and the broader Epembe project hinges on a well-defined delineation of stakeholder roles and responsibilities, fostering a collaborative governance model. The **Ministry of Education, Innovation, Youth, Sports, and Arts and Culture** serves as the proponent, bearing primary responsibility for project conceptualization, funding allocation, and strategic oversight. This ministry has commissioned the development of the 350,000 m² site to address educational deficits, ensuring alignment with national development goals such as Vision 2030. **Erongo Consulting Group (Pty) Ltd**, acting as the Environmental Assessment Practitioner (EAP), is tasked with conducting the ESIA, including baseline data collection, impact assessment, and the formulation of the Environmental Management Plan (EMP). The EAP's role extends to coordinating public consultations, as evidenced by the engagement process concluding on 5 June 2025, and liaising with regulatory bodies to ensure compliance.

The **Ministry of Environment, Forestry & Tourism (MEFT)** functions as the regulatory authority, responsible for reviewing the ESIA report (Reference No: 250621005958) and issuing the Environmental Clearance Certificate upon satisfactory assessment. MEFT's mandate includes

enforcing the Environmental Management Act (No. 7 of 2007) and monitoring post-approval compliance. The **Ohangwena Regional Council**, as the local governance entity, oversees land use planning within the communal tenure system, ensuring that the project respects traditional land rights and mitigates conflicts with grazing activities near the site. **Traditional Authorities**, representing the indigenous communities, play a pivotal role in mediating land use disputes and providing cultural insights, particularly regarding the oshana's significance 300–400 meters southeast. **Interested and Affected Parties (I&APs)**, including local homesteaders (200–300 meters northwest) and downstream water users, contribute through public input, shaping mitigation strategies and enhancing project legitimacy, as mandated by the Environmental Management Act Regulations (2012).

This multi-stakeholder framework promotes accountability and transparency, with each entity's responsibilities interlinked to achieve a sustainable outcome. The EAP facilitates communication among these stakeholders, ensuring that engineering designs (e.g., WWTP treatment stages) and social interventions (e.g., employment opportunities) are responsive to local needs and regulatory requirements.

1.6. Limitations and Data Gaps

The ESIA process, while comprehensive, is subject to inherent limitations and data gaps that may influence the accuracy of impact predictions and mitigation strategies. A primary limitation is the **seasonal variability in oshana hydrology**, with the wetland's water levels and ecological function fluctuating significantly between the rainy season (November - April, 400 - 600 mm precipitation) and the dry season. Field surveys conducted from May to June 2025 at captured baseline conditions during a transitional period, potentially underrepresenting peak flood events that could affect effluent dispersion and oshana biodiversity. This variability necessitates longitudinal monitoring to validate model predictions of effluent impact (Glasson et al., 2012).

Another significant gap is the **limited historical ecological data** for the site and its 5-kilometer radius of influence. The absence of long-term records on faunal populations (e.g., *Lepus capensis*, *Francolinus* spp.) and floral composition (e.g., *Colophospermum mopane*, *Acacia* spp.) hinders a precise assessment of baseline biodiversity prior to the 20-hectare vegetation clearing. Similarly, socio-economic data on homesteads 200 - 300 meters west and northwest is constrained by the lack of recent census information, limiting the quantification of affected populations and their reliance on the oshana for livestock watering. These gaps are compounded by the unavailability of pre-existing water quality data for the oshana, critical for establishing a reference against which WWTP effluent (BOD <30 mg/L, TSS <25 mg/L) will be measured.

To address these limitations, the ESIA proposes an **adaptive management approach**, incorporating ongoing monitoring of oshana hydrology, water quality, and biodiversity post-construction, as recommended by Glasson et al. (2012). This will involve the deployment of

automated sensors for real-time data collection and annual ecological surveys to track species responses. Data gaps in socio-economic impact will be mitigated through a baseline socioeconomic study to be conducted prior to construction, engaging I&APs to gather oral histories and current land use patterns. These strategies ensure that uncertainties are progressively resolved, enhancing the robustness of the Environmental Management Plan (EMP) and supporting MET's decision-making process for the Environmental Clearance Certificate.

2. PROJECT DESCRIPTION

This chapter provides an exhaustive technical description of the proposed wastewater treatment plant (WWTP) project for the new secondary school at Epembe, Ohangwena Region, Namibia, located on a 350,000 m² (35-hectare) communal land parcel at coordinates 17°47'27"S, 16°27'04"E. The project involves the design, construction, operation, and maintenance of a WWTP to manage 60 - 80 m³/day of wastewater generated by 600 learners and staff, integrated with the school's sanitation infrastructure.

The WWTP features a 200-m high-density polyethylene (HDPE) pipeline (150 mm diameter), a 20-kW solar-diesel hybrid power grid, and ancillary facilities, with effluent discharged into the oshana 300 - 400 m southeast and 15–20 m³/month of sludge managed on-site. The description is grounded in feasibility studies conducted within a 5-kilometer radius, reflecting the region's semi-arid climate (400 - 600 mm annual rainfall), deep sandy soils (silt <10%, cohesion <5 kPa), and ecological sensitivity. The project complies with the Environmental Management Act (No. 7 of 2007), its Regulations (2012), the Water Resources Management Act (No. 24 of 2004), and international standards, including the International Association for Impact Assessment (IAIA) guidelines (2015) and the International Finance Corporation (IFC) Performance Standards (2012).

2.1. Project Rationale and Objectives

The WWTP addresses a critical sanitation deficit in Epembe, where only 30% of the 1,500 - 2,000 residents within 5 km have access to treated wastewater systems, relying on pit latrines with 70% failure rates during rains. The project objectives are: (1) to treat 60–80 m³/day of wastewater to meet Namibia's discharge standards (BOD <25 mg/L, TSS <20 mg/L, E. coli <150 CFU/100 mL); (2) to support the educational infrastructure for 600 learners with a reliable sanitation system; (3) to minimize environmental impact on the oshana ecosystem through a 50–80 m buffer and real-time monitoring; (4) to generate 6 - 12 local employment opportunities during construction and operation; and (5) to align with the National Development Plan 5 (2021

- 2026) for sustainable water management. The total project is expected to run for 30 years (operational lifespan) (2026 - 2056).

Figure 2: Site Plan of the Proposed Epembe Secondary School, Ohangwena Region, Namibia, located at 17°47'27"S, 16°27'04"E, depicting the 35-hectare development area east of the D3602 road, including the wastewater treatment plant





Figure 3: Potable Water Reticulation Layout for the Proposed Epembe Secondary School, Ohangwena Region, Namibia, illustrating the water distribution network across the 35-hectare site



2.2. Project Location and Site Characteristics

2.2.1. Geographical Context

The proposed Epembe Secondary School site is geographically situated approximately 5 km northeast of Epembe village in the Ohangwena Region, Namibia, accessible via the D3602 road, which branches from the B1 highway near Oshikango, approximately 50 - 60 km to the east. Located at coordinates 17°47'27"S, 16°27'04"E, the site lies within the semi-arid Cuvelai Basin, characterized by a flat to gently undulating terrain with a 2–5% southwest gradient toward seasonal oshana wetlands. The region experiences an annual rainfall of 400–600 mm, primarily from November to April, and temperatures ranging from 15°C to 35°C, typical of northern Namibia's savanna-woodland landscape. The B1 highway, a major north-south route, connects Oshikango to the Angolan border, while the D3602 serves as a local access route, reflecting the area's rural setting within the communal land tenure system overseen by the Ohangwena Regional Council.

2.3. Site Conditions

2.3.1. Soil Profile

The site, located at coordinates 17°47'27"S, 16°27'04"E east of the D3602 road, features a sandy loam soil profile with less than 10% silt content, a cohesion strength below 5 kPa, and a permeability of approximately 10^{-6} m/s, as determined by geotechnical coring conducted on May 25, 2025. This loose, low-cohesion soil, typical of the Cuvelai Basin's deep sandy substrates, poses challenges for structural stability, particularly for the wastewater treatment plant (WWTP) foundations. Stabilization measures, such as compacted sand bedding (95% Proctor density) and reinforced concrete footings (C25/30, 300 mm wide, 500 mm thick), are essential to mitigate settlement and erosion risks, especially given the 2–5% southwest gradient toward the oshana.

2.3.2. Hydrology

Hydrological assessments indicate groundwater at depths of 30–50 m, with salinity levels ranging from 1,500 to 2,500 $\mu\text{S}/\text{cm}$, measured using conductivity meters. The oshana, a seasonal wetland 300 - 400 m southeast of the site as mapped, forms part of the Cuvelai Basin's hydrological system, flooding during the rainy season (November - April) with surface water depths of 0.5 - 1 m. This dynamic wetland, supporting seasonal aquatic ecosystems, influences effluent discharge planning, requiring a 50-m vegetated buffer to prevent contamination and maintain dissolved oxygen levels (4 - 6 mg/L). The site's gradient and proximity to the oshana necessitate careful drainage design to manage runoff and protect groundwater quality.

2.3.3. Climate

The region experiences a semi-arid climate with an annual rainfall of 400 - 600 mm, peaking from December to March, as recorded by local weather stations between 2020 and 2025. Temperatures range from 15°C to 35°C, with daily fluctuations influenced by the dry season (May - October). Wind speeds of 15 - 20 km/h, prevalent during the dry months, contribute to dust generation and erosion potential. These climatic conditions demand the use of drought-resistant materials (e.g., UV-stabilized HDPE pipelines) and erosion control measures (e.g., silt fences) to ensure the longevity of infrastructure and minimize environmental impact during construction and operation.

2.3.4. Vegetation

The site is dominated by 70% savanna-woodland cover, comprising species such as *Colophospermum mopane* and *Acacia tortilis*, as identified through 100-m transects conducted April / May, 2025. This vegetation supports a biodiversity profile including small mammals (e.g., *Lepus capensis*), birds (e.g., *Francolinus* spp.), and reptiles (e.g., *Agama* spp.). Approximately 0.5 ha has been cleared for the WWTP footprint, with the remaining area preserved to maintain ecological connectivity. The clearing, executed with a 50-m buffer around the oshana, minimizes disruption to the wetland's flora and fauna, aligning with mitigation strategies outlined in the Environmental Management Plan.

Table 1: Site Environmental Parameters

Parameter	Unit	Value/Range	Measurement Method	Source
Soil Silt Content	%	<10%	Geotechnical Coring	April / May, 2025
Soil Cohesion	kPa	<5	Shear Vane Test	April / May, 2025
Soil Permeability	m/s	10^{-6}	Constant Head Permeameter	April / May, 2025
Groundwater Depth	m	30 - 50	Depth Sounding	2013
Groundwater Salinity	$\mu\text{S/cm}$	1,500 - 2,500	Conductivity Meter	2013
Oshana Distance	m	300 - 400	GPS Mapping	April / May, 2025
Annual Rainfall	mm	400 - 600	Weather Station	2020 - 2025
Temperature Range	$^{\circ}\text{C}$	15 - 35	Weather Station	2020 - 2025
Wind Speed	km/h	15 - 20	Anemometer	May 20, 2025
Vegetation Cover	%	70% (mopane, acacia)	100-m Transects	April / May, 2025
Biodiversity Index	Species/ha	5 - 10	Species Count	April / May, 2025

2.4. Infrastructure Description

2.4.1. Wastewater Treatment Plant

The WWTP is a conventional activated sludge system with a design capacity of 80 m³/day, scalable to 100 m³/day. Detailed components include:

- **Inlet and Screening:** 5 mm stainless steel bar screens (2 m wide, 1.5 m high) remove 0.5–1 m³/day of coarse solids into a 2 m³ hopper.
- **Primary Sedimentation Tank:** Circular, 10 m³ capacity, 3 m diameter, 2 m depth, with a 1 m³ sludge hopper and 50–60% solids removal efficiency.
- **Aeration Tank:** Rectangular, 20 m³ volume (5 m × 2 m × 2 m), equipped with 5 kW fine-bubble diffusers maintaining 2–3 mg/L dissolved oxygen (DO) and MLSS 2,500–3,500 mg/L.
- **Secondary Clarifier:** 15 m³, 4 m diameter, 1.5 m side water depth, achieving 80–90% TSS reduction with a 2 m³ sludge return pump.
- **UV Disinfection Unit:** 2 kW system delivering 45 mJ/cm², treating 80 m³/day with a 1 m² contact chamber, reducing E. coli to <150 CFU/100 mL.
- **Sludge Digester:** 5 m³ anaerobic digester (2 m × 1.5 m × 2 m), producing 15–20 m³/month of dewatered sludge (20–30% solids) with a 1 kW mixer.

2.4.2. Pipeline System

The 200-m HDPE pipeline (PN10, SDR 11) is buried at 1.5 m depth, with a 1% gradient (1:100) ensuring 0.6 - 0.8 m/s flow velocity. It features heat-fused joints, 5 manholes (1 m diameter, 1.2 m depth), and a 10-bar pressure rating, modeled with Hec-RAS v6.0.

2.4.3. Power Supply

The 20-kW hybrid system includes:

- **Solar Array:** 100 m² of monocrystalline panels (12 kW peak, 25% efficiency), mounted on 2 m steel frames.
- **Diesel Generator:** 5 kW, 10 L/hour consumption, with a 200 L tank.
- **Battery Bank:** 50 kWh lead-acid, 48 V configuration, with a 5-kW inverter.
- **Emissions:** <15 kg CO₂/day, monitored with FLIR thermal imaging.

2.4.4. Ancillary Facilities

- **Control Room:** 20 m² insulated unit with SCADA system, 2 kW air conditioning, and 10 m² solar roof.
- **Sludge Storage:** 25 m³ concrete tank (5 m × 3 m × 2 m) with 1 m³ leachate sump and pH neutralization (6–8).
- **Access Road:** 2-km gravel upgrade to 4 m width, 15 cm base course (crushed stone), and 5 cm surface layer.

2.5. Civil Engineering Design

2.5.1. Foundation and Structural Elements

- **Footings:** 1 m deep strip footings (300 mm wide, 500 mm thick) with C25/30 concrete (350 kg/m³ cement, 0.45 water-cement ratio), reinforced with 12 mm rebar at 200 mm centers, designed for a 10 kPa live load.
- **Tank Walls:** 200 mm thick C25/30 concrete, 2 m high, with 10 mm steel lining for corrosion resistance, factor of safety 1.5 against overturning.
- **Pipeline Trench:** 1.5 m deep, 0.5 m wide, backfilled with 10 cm sand bedding (compacted to 95% Proctor) and 20 cm native soil cover.

2.5.2. Hydraulic Design

- **Pipeline:** 1:100 gradient, 0.6–0.8 m/s velocity, with a Manning's roughness coefficient of 0.009, preventing siltation.
- **WWTP Retention:** 8-hour hydraulic retention time, peak flow factor 1.5 (120 m³/day), with 20 m³ surge capacity.

2.5.3. Materials Specification

Table 2: Materials Specification

Component	Material	Specification	Quantity	Source	Design Life
Concrete (Footings)	C25/30	350 kg/m ³ cement, 0.45 w/c ratio	200 m ³	Local Quarry	50 years
HDPE Pipe	PN10, SDR 11	UV-resistant, 150 mm diameter	200 m	SAPPMA Certified	50 years
Steel (Supports)	S355, Galvanized	100 µm epoxy coating	10 t	ArcelorMittal	30 years
Rebar	12 mm, Deformed	200 mm centers	5 t	Local Supplier	50 years

2.6. Construction Phases

2.6.1. Phase 1: Site Preparation (3 Months)

- **Clearing:** Remove 0.5 ha vegetation (2,000 trees >5 m), preserving 50 m oshana buffer, with 10 m³ wood chips for mulch.
- **Earthworks:** Excavate 1,500 m³ (500 m³ WWTP, 1,000 m³ pipeline), using 20 m³ excavators, with 10 m³ silt traps and 5 m berms.
- **Foundation Laying:** Pour 200 m³ C25/30 concrete, curing 28 days with wet blankets, achieving 95% compressive strength.

2.6.2. Phase 2: Infrastructure Installation (6 Months)

- **WWTP Assembly:** Install 5 mm screens, 10 m³ sedimentation tank, and 20 m³ aeration tank, tested for leaks (10 bar) with 50 m³ water.
- **Pipeline Laying:** Install 200 m HDPE with heat fusion (200°C, 90 seconds/joint), pressure-tested to 12 bar, with 5 manholes.
- **Power Setup:** Erect 100 m² solar array on 2 m steel frames, connect 5 kW generator, and install 50 kWh battery bank.

2.6.3. Phase 3: Commissioning (2 Months)

- **Testing:** 72-hour trial run with 80 m³/day, verifying MLSS (2,500–3,500 mg/L), BOD <25 mg/L, and UV efficacy (45 mJ/cm²).
- **Training:** 150 hours for 6 -12 operators on SCADA, pump maintenance, and safety, certified by Aqua Engineering.

Table 3: Construction Phase Schedule

Phase	Duration	Activities	Resources	Milestone
-------	----------	------------	-----------	-----------

Site Preparation	3 months	Clearing, earthworks, foundation	Excavators, concrete mix	95% Foundation Strength
Infrastructure Install	6 months	WWTP assembly, pipeline, power setup	Cranes, welders, panels	Leak Test (10 bar)
Commissioning	2 months	Testing, training	SCADA, trainers	Effluent Compliance

2.7. Operation Procedures

2.7.1. Wastewater Treatment Process

- **Screening:** Daily removal of 0.5–1 m³ solids with a front-end loader, disposed in a 2 m³ hopper.
- **Aeration:** Maintain 2–3 mg/L DO with 5 kW blowers (10,000 m³/h), adjusted via dissolved oxygen sensors.
- **Sedimentation:** Achieve 50–60% solids removal in the 10 m³ tank, with 1 m³ sludge pumped hourly.
- **Disinfection:** Apply 45 mJ/cm² UV with 2 kW lamps, monitored with a dosimeter, treating 80 m³/day.
- **Sludge Handling:** Dewater 15–20 m³/month to 20–30% solids using a 2-kW centrifuge, storing in a 25 m³ tank.

2.7.2. Staffing and Scheduling

- **Operators:** 6–12 staff (3 shifts of 4), 8-hour shifts, 7 days/week, with 2 supervisors.
- **Schedule:** Continuous operation, with weekly maintenance slots (8:00 AM–12:00 PM).

2.8. Maintenance Protocols

2.8.1. Routine Maintenance

- **Weekly:** Inspect pipeline pressure (10–12 bar), clean 5 mm screens (0.5 m³ debris), and replace UV lamps (500-hour lifespan).
- **Monthly:** Service 5 kW blowers (lubrication, filter change), test sludge solids (20–30%), and calibrate SCADA sensors.
- **Annual:** Overhaul aeration system (replace diffusers), inspect 50 kWh battery bank, and recoat steel with 100 µm epoxy.

2.8.2. Preventive Measures

- **Corrosion Protection:** Apply 100 µm epoxy to S355 steel, monitored quarterly with ultrasonic gauges (<0.1 mm/year).

- **Emergency Stock:** Maintain 50 m³ spares (10 m HDPE, 5 valves, 2 UV lamps) and a 10-kW backup generator.
- **Training:** 50 hours/year on pump repair, SCADA troubleshooting, and safety, with annual certification.

Table 4: Maintenance Schedule

Frequency	Task	Equipment	Target	Responsible Party
Weekly	Pipeline Pressure Check	Pressure Gauge	10 - 12 bar	Operators
Monthly	Sludge Solids Test	Centrifuge	20 - 30%	Aqua Engineering
Annual	Battery Bank Inspection	Multimeter	95% Capacity	Erongo Consulting

2.9. Project Timeline and Estimated Cost Estimate

- **Timeline:** 11 months for construction (Q3 2025–Q1 2026), 30 years for operation (2026–2056), 6 months for decommissioning (Q2 2057).
- **Estimated Cost Estimate:** N\$5.2 million, detailed below.

Table 5: Estimated Cost Estimate Breakdown

Category	Sub-Component	Cost (N\$)	Percentage	Notes
Construction	Earthworks	500,000	9.6%	1,500 m ³ excavation
	Concrete Footings	800,000	15.4%	200 m ³ C25/30
	Pipeline Installation	700,000	13.5%	200 m HDPE
WWTP Units	Screening Unit	300,000	5.8%	5 mm screens
	Aeration Tank	600,000	11.5%	20 m ³ , 5 kW blowers
	UV Disinfection	400,000	7.7%	2 kW system
Power Supply	Solar Array	500,000	9.6%	100 m ² panels
	Diesel Generator	300,000	5.8%	5 kW, 200 L tank
Commissioning	Testing and Training	400,000	7.7%	72-hour trial, 150 hours
Contingency	Unforeseen Costs	700,000	13.5%	10% buffer
Total		5,200,000	100%	

2.10. Institutional Responsibilities

Table 6: Institutional Responsibilities

Entity	Role	Contact Person	Phone	Email	Address
Erongo Consulting Group (Pty) Ltd	Project Management, Design	Sarah Amutenya	+264 81 878 66 76	info@erongoconsultinggroup.co.za	P.O. Box 3456, Swakopmund
Aqua Engineering	WWTP Design, Installation	Linda Shikongo	+264 81 234 5678	tech@aquaeng.com.na	P.O. Box 1234, Oshakati
Arteer Engineering	Civil Works, Pipeline	Peter Vries	+264 81 123 4567	pvries@artee.com.na	P.O. Box 789, Walvis Bay
Ministry of Education	Funding, Oversight	Maria Nangolo	+264 61 279 200	pmu@moe.gov.na	P.O. Box 656, Windhoek
Oshana Regional Council	Site Coordination, Access	Thomas Haushona	+264 65 250 100	planning@orc.na	P.O. Box 66, Eenhana

References

- Glasson, J., Therivel, R., & Chadwick, A. (2012). *Introduction to environmental impact assessment* (4th ed.). Routledge.
- International Association for Impact Assessment (IAIA). (2015). *Principles of environmental impact assessment best practice*. Retrieved from <https://www.iaia.org>.
- International Finance Corporation (IFC). (2012). *Performance standards on environmental and social sustainability*. World Bank Group.
- Metcalf & Eddy, Inc. (2014). *Wastewater engineering: Treatment and resource recovery* (5th ed.). McGraw-Hill Education.
- SANS 1200. (2019). *Standardized specification for civil engineering construction*. South African National Standards.

3. POLICY, LEGAL, AND ADMINISTRATIVE FRAMEWORK

This chapter outlines the policy, legal, and administrative framework governing the Environmental and Social Impact Assessment (ESIA) for the proposed secondary school and wastewater treatment plant (WWTP) at Epembe, Ohangwena Region, Namibia. The framework ensures that the development, located on a 350,000 m² (35-hectare) communal land site at coordinates 17°47'27"S, 16°27'04"E, complies with national legislative mandates and international best practices. This alignment is critical given the site's proximity to an oshana (300 - 400 meters southeast) within the Cuvelai Basin and its implications for environmental and social sustainability. The involvement of engineering firms such as Artee Engineering and aqua engineering, alongside the project civil engineer, further strengthens the technical foundation of the framework.

3.1. National Legislation

The ESIA is anchored in a comprehensive suite of Namibian statutes that regulate environmental protection, water management, public health, and infrastructure development. These laws provide the legal basis for assessing and mitigating the impacts of the proposed project. Table below summarizes the key legislative instruments and their specific relevance.

Table 7: Summary of National Legislative Framework

Legislation	Reference	Key Provisions	Relevance to Epembe Project
Environmental Management Act	No. 7 of 2007	Mandates ESIA for projects with significant environmental impact; requires EMP.	Governs the ESIA process, including public consultation ending 5 June 2025.
Environmental Impact Assessment Regulations	Government Notice No. 30 of 2012	Specifies scoping, assessment, and reporting requirements for EIAs.	Guides the structure and submission of this ESIA report (Ref No: 250621005958).
Water Resources Management Act	No. 11 of 2013	Regulates water use and effluent discharge; sets standards (BOD <30 mg/L, TSS <25 mg/L).	Ensures WWTP effluent quality for oshana discharge, overseen by aqua engineering.
Public and Environmental Health Act	No. 1 of 2015	Requires safe wastewater management to protect public health.	Mitigates health risks from untreated sewage, a focus for Artee Engineering's civil design.
Namibia Water Corporation Act	No. 12 of 1997	Governs water supply and sanitation infrastructure development.	Supports WWTP integration with potable water layout (Drawing C-20), coordinated by aqua engineering.
Local Authorities Act	No. 23 of 1992	Facilitates coordination with regional and local governance.	Engages Ohangwena Regional Council for land use planning in communal area.
National Heritage Act	No. 27 of 2004	Protects archaeological and cultural resources during construction.	Requires pre-construction heritage survey for the 200,000 m ² site, reviewed by project engineer.
Pollution Control and Waste Management Bill	Draft (in progress)	Provides guidelines for waste and effluent management.	Informs sludge disposal strategies, a responsibility of Artee Engineering.

The Environmental Management Act (No. 7 of 2007) mandates an ESIA for projects with significant environmental footprints, such as the 20-hectare vegetation clearing and effluent discharge into the oshana. The Environmental Impact Assessment Regulations (2012) detail the procedural requirements, including baseline studies and public participation, which concluded on 5 June 2025. The Water Resources Management Act (No. 11 of 2013) establishes effluent quality standards to protect the Cuvelai Basin, a task supported by aqua engineering's expertise in wastewater treatment design. The Public and Environmental Health Act (No. 1 of 2015) ensures public health safeguards, aligning with Artee Engineering's civil infrastructure planning. Other legislation, such as the Namibia Water Corporation Act (No. 12 of 1997) and the National Heritage Act (No. 27 of 2004), supports water supply integration and cultural resource protection, respectively.

3.2. International Guidelines and Standards

The ESIA incorporates international guidelines and standards to enhance its global applicability and ensure alignment with best practices. These frameworks complement national legislation and guide the engineering and environmental management aspects of the project.

- **International Association for Impact Assessment (IAIA) Principles (2015):** These principles emphasize a participatory and transparent ESIA process, reflected in the stakeholder engagement concluding on 5 June 2025. The use of a risk-based impact assessment matrix aligns with IAIA's scientific rigor.
- **International Finance Corporation (IFC) Performance Standards (2012):** Performance Standard 1 requires the assessment of environmental and social risks, including impacts on the oshana's biodiversity. Performance Standard 3 mandates pollution prevention, guiding the WWTP design (e.g., activated sludge with MLSS of 2,000 - 3,000 mg/L), a focus for aqua engineering.
- **Ramsar Convention on Wetlands (1971):** As a signatory, Namibia must conserve wetlands like the oshana, 300 - 400 meters southeast, requiring mitigation to preserve its ecological function, a consideration for the project civil engineer.
- **Equator Principles (2020):** These principles ensure environmental and social due diligence for project financing, supporting the evaluation of alternatives and EMP development, overseen by Artee Engineering.
- **United Nations Sustainable Development Goals (SDGs) (2015):** The project advances SDG 4 (Quality Education) through school infrastructure and SDG 6 (Clean Water and Sanitation) via the WWTP, aligning with national and international development goals.

Table 8 illustrates the alignment of these standards with project components, highlighting engineering contributions.

Table 8: Alignment of International Standards with Project Components

Standard/Guideline	Reference	Relevant Component	Application to Epembe Project	Engineering Role
IAIA Principles	2015	Stakeholder Engagement	Guides public consultation process ending 5 June 2025.	Artee Engineering facilitates input.
IFC Performance Standard 1	2012	Risk Assessment	Assesses impacts on oshana biodiversity and community health.	Project civil engineer oversees risks.
IFC Performance Standard 3	2012	Pollution Prevention	Optimizes WWTP design for effluent quality (BOD <30 mg/L, TSS <25 mg/L).	Aqua engineering designs treatment.
Ramsar Convention	1971	Wetland Conservation	Protects oshana ecosystem 300–400 m southeast.	Civil engineer ensures mitigation.
Equator Principles	2020	Financing and Due Diligence	Ensures sustainable financing for 350,000 m ² site development.	Artee Engineering supports compliance.
UN SDGs (4 and 6)	2015	Education and Sanitation	Supports school infrastructure and WWTP sanitation goals.	Aqua engineering integrates systems.

3.3. Institutional Responsibilities

The implementation of the ESIA and the Epembe project relies on a coordinated institutional framework, with specific roles assigned to engineering entities. The **Ministry of Environment, Forestry & Tourism (MEFT)** is the regulatory authority, responsible for reviewing the ESIA report (Reference No: 250621005958) and issuing the Environmental Clearance Certificate. MET's Department of Environmental Affairs monitors compliance with the Environmental Management Act (No. 7 of 2007) and WWTP effluent standards.

The **Ministry of Education, Innovation, Youth, Sports, and Arts and Culture**, as the proponent, oversees project funding and strategic alignment with Vision 2030. **Erongo Consulting Group (Pty) Ltd**, the Environmental Assessment Practitioner (EAP), conducts the ESIA, develops the EMP, and coordinates stakeholder engagement, concluded on 5 June 2025. **Artee Engineering**, as the project civil engineering firm, leads construction planning and infrastructure design, ensuring sustainable site development on the 350,000 m² parcel. The **project civil engineer** from Artee Engineering supervises civil works, including road access and building foundations, while integrating mitigation measures for the oshana. **Aqua engineering**, specializing in water and wastewater systems, designs the WWTP, optimizing the activated sludge process and effluent treatment to meet Water Resources Management Act standards.

The **Ohangwena Regional Council** manages land use within the communal tenure system, coordinating with traditional authorities who mediate cultural concerns, particularly regarding the oshana. **Interested and Affected Parties (I&APs)**, including homesteaders 200–300 meters northwest, provide input to shape mitigation strategies. The **Namibia Water Corporation**, under the Namibia Water Corporation Act (No. 12 of 1997), supports water supply integration (e.g., Drawing C-20), while the **National Heritage Council**, per the National Heritage Act (No. 27 of 2004), conducts heritage assessments.

Table 9 outlines the institutional responsibilities, highlighting engineering roles.

Table 9: Institutional Responsibilities

Institution	Role	Key Responsibilities	Contact/Coordination	Engineering Contribution
Ministry of Environment, (MET)	Regulatory Authority	ESIA review, Environmental Clearance Certificate issuance.	Department of Environmental Affairs	Oversees engineering compliance.
Ministry of Education, Innovation, Youth, Sports, and Arts and Culture	Proponent	Project funding, strategic oversight.	Project Management Unit	Funds engineering designs.
Erongo Consulting Group (Pty) Ltd	Environmental Assessment Practitioner	ESIA conduct, EMP development, stakeholder engagement.	erongoconsulting@gmail.com +264 81 878 66 76	Coordinates with Artee and aqua engineering.
Artee Engineering	Civil Engineering Firm	Construction planning, infrastructure design.	Contact via project civil engineer	Leads site development.
Project Civil Engineer (Artee)	Civil Engineering Supervision	Oversees construction, mitigation integration.	On-site coordination	Ensures oshana protection.
Aqua Engineering	Water/Wastewater Specialist	WWTP design, effluent treatment optimization.	Technical support division	Designs WWTP systems.
Ohangwena Regional Council	Local Governance	Land use planning, communal land management.	Regional Planning Office	Approves engineering plans.
Traditional Authorities	Cultural Oversight	Mediation, cultural resource protection.	Community Liaison	Advises civil engineer on heritage.
Interested and Affected Parties (I&As)	Public Input	Feedback on impacts, mitigation suggestions.	Public Consultation Records	Informs engineering adjustments.
Namibia Water Corporation	Technical Support	Water supply and sanitation integration.	Technical Support Division	Supports aqua engineering.
National Heritage Council	Heritage Protection	Pre-construction heritage survey.	Heritage Assessment Unit	Guides civil engineer on heritage sites.

This framework ensures a collaborative approach, with Artee Engineering, the project civil engineer, and aqua engineering / or any other consultant playing pivotal roles in technical execution and compliance.

References

- Environmental Management Act (No. 7 of 2007). Republic of Namibia.
- Equator Principles (2020). *Equator Principles: A Financial Industry Benchmark for Determining, Assessing and Managing Environmental and Social Risk in Projects*. Retrieved from <https://equator-principles.com>.
- International Association for Impact Assessment (IAIA). (2015). *Principles of Environmental Impact Assessment Best Practice*. Retrieved from <https://www.iaia.org>.
- International Finance Corporation (IFC). (2012). *Performance Standards on Environmental and Social Sustainability*. World Bank Group.
- Ramsar Convention on Wetlands (1971). *Convention on Wetlands of International Importance Especially as Waterfowl Habitat*. Retrieved from <https://www.ramsar.org>.
- United Nations. (2015). *Transforming Our World: The 2030 Agenda for Sustainable Development*. United Nations General Assembly.
- Water Resources Management Act (No. 11 of 2013). Republic of Namibia.

4. BASELINE ENVIRONMENTAL AND SOCIAL CONDITIONS

This chapter provides a comprehensive baseline assessment of the environmental, social, and cultural conditions for the proposed development of a new secondary school and wastewater treatment plant (WWTP) at Epembe, Ohangwena Region, Namibia. The analysis distinguishes between the specific project site (a 350,000 m² parcel of communal land at coordinates 17°47'27"S, 16°27'04"E) and the broader Ohangwena Region, drawing on data collected through field surveys, satellite imagery, GIS mapping, and extensive community consultations conducted between May and June 2025. The methodology aligns with internationally recognized standards for baseline characterization, as outlined by Glasson et al. (2012) and the International Association for Impact Assessment (IAIA) guidelines (2015), ensuring a robust foundation for subsequent impact assessment and mitigation planning.

4.1. Epembe Site Conditions

4.1.1. Environmental Conditions

The Epembe site is situated within a semi-arid ecological zone, characterized by an annual precipitation range of 400 - 600 mm, with the majority occurring during the rainy season from November to April. The site's climate exhibits marked seasonality, with dry periods (May–October) contributing to heightened aridity and wind erosion. The terrain consists of deep sandy soils with a silt content below 10%, exhibiting low cohesion and a southwest gradient that directs surface runoff toward an adjacent oshana located 300 - 400 meters southeast.

Topographic surveys indicate elevations ranging from 1,100 to 1,150 meters above sea level, with gentle undulations facilitating episodic water flow during rainfall events. Surface water is virtually absent outside the oshana, which serves as a seasonal wetland supporting ephemeral ponds and intermittent streams. Groundwater resources are accessible at depths of 30–50 meters, though salinity levels ranging from 1,500 to 2,500 µS/cm render the water marginally suitable for domestic use, necessitating treatment for potable applications (FAO, 2014).

Air quality at the site is predominantly unpolluted, with baseline particulate matter (PM₁₀) concentrations averaging below 50 µg/m³, consistent with a rural setting devoid of significant industrial activity. However, dry-season wind speeds, often exceeding 15 km/h, mobilize fine sand particles, elevating dust levels and posing a potential respiratory hazard during construction. Ambient noise levels range from 40 to 50 decibels (dB), reflecting natural sounds such as wind and wildlife, with occasional increases to 55 - 60 dB near national roads D3602 and D3604, located 1 - 2 kilometers from the site. These roads, visible on satellite imagery, serve as critical access routes and may influence baseline acoustic conditions.

Vegetation is dominated by sparse savanna-woodland, with a canopy cover estimated at 70% across the 350,000 m² site. Dominant species include *Colophospermum mopane*, *Acacia* spp., and *Terminalia sericea*, adapted to the region's water-scarce environment. The proposed clearing of 20 hectares for construction will significantly reduce this habitat, impacting ecological connectivity. Faunal diversity includes small mammals (e.g., *Lepus capensis*), avian species (e.g., *Francolinus* spp.), and reptiles (e.g., *Agama* spp.), with population densities constrained by habitat fragmentation.

The oshana, a critical ecological feature, supports a richer biodiversity during the wet season, hosting amphibians (e.g., *Pyxicephalus adspersus*), invertebrates, and migratory waterfowl (e.g., *Anas undulata*) from December to March. Preliminary water quality assessments of the oshana reveal a pH range of 6.8 - 7.2 and dissolved oxygen levels of 4 - 6 mg/L, indicative of a moderately productive aquatic ecosystem subject to seasonal fluctuations (Wetlands International, 2018).

Figure 4: Aerial view of Epembe site showing vegetation distribution and oshana layout




Table 10: Environmental Parameters at Epembe Site

Parameter	Baseline Value/Description	Measurement Method	Notes
Precipitation	400–600 mm/year	Meteorological data	Rainy season (Nov–Apr)
Soil Type	Deep sandy (silt <10%)	Soil sampling	Southwest gradient to oshana
Elevation	1,100–1,150 m ASL	Topographic survey	Gentle undulations
Groundwater Depth	30–50 m	Borehole logs	Salinity 1,500–2,500 µS/cm
Air Quality (PM10)	<50 µg/m ³	Air quality monitoring	Dry season dust concern
Noise Levels	40–50 dB (55–60 dB near roads)	Sound level meter	Natural background

Vegetation Cover	70% (mopane, acacia, terminalia)	Transect surveys	20 ha to be cleared
Fauna	Hares, birds, reptiles	Camera traps, visual surveys	Oshana biodiversity peak Dec–Mar
Oshana Water Quality	pH 6.8–7.2, DO 4–6 mg/L	Field testing	Seasonal wetland

4.1.2. Socio-Economic Conditions

The Epembe site is embedded within a rural socio-economic context, with an estimated population of 1,500 - 2,000 residing within a 5-kilometer radius, concentrated in homesteads located 200–300 meters northwest. Livelihoods are predominantly subsistence-based, relying on rain-fed agriculture (e.g., millet, sorghum) and pastoralism (e.g., cattle, goats), with the oshana serving as a vital water source for livestock and small-scale irrigation. The communal land tenure system, administered by the Ohangwena Regional Council, supports traditional grazing practices, though land use pressure is intensifying due to a population growth rate of 0.5–1% annually, driven by natural increase and seasonal migration.

Educational infrastructure is severely limited, with the nearest secondary school situated 15 kilometers away, resulting in secondary enrollment rates of 40–50% and necessitating the proposed 600-learner facility with hostel accommodations. Employment opportunities are scarce, with households dependent on seasonal agricultural labor, informal trade, and remittances from urban areas. Infrastructure is rudimentary, comprising unpaved access roads, shallow hand-dug wells, and basic water points, with the absence of centralized sanitation exacerbating public health risks and justifying the WWTP development.

Figure 5: Community homesteads near Epembe site depicting rural living conditions



Figure 6: Homesteads in the Vicinity of Epembe Secondary School Site, Ohangwena Region, Namibia



Table 11: Socio-Economic Parameters at Epembe Site

Parameter	Baseline Value/Description	Measurement Method	Notes
Population	1,500–2,000	Household surveys	Homesteads 200–300 m NW
Livelihood	Agriculture, pastoralism	Community interviews	Oshana water use
Population Growth	0.5–1% annually	Census data	Increasing land use pressure
Education Access	Nearest school 15 km	GIS mapping	Justifies 600-learner school
Employment	Seasonal labor, remittances	Economic surveys	Limited opportunities
Infrastructure	Unpaved roads, no sanitation	Site inspection	WWTP planned

4.1.3. Cultural and Historical (Heritage) Conditions

The cultural and historical landscape of the Epembe site reflects a blend of tangible and intangible heritage elements. Initial archaeological surveys conducted in April/May 2025 identified no significant surface artifacts or cultural heritage features within the 350,000 m² site, though subsurface investigations remain incomplete. The oshana, located 300 - 400 meters southeast,

holds profound cultural significance as a site for water-related rituals, including rain-making ceremonies and communal gatherings, as documented through consultations with traditional authorities. Oral histories from local elders suggest the presence of unrecorded burial sites and historical settlement remnants near homesteads, potentially dating to pre-colonial migration periods. These findings underscore the need for a comprehensive pre-construction heritage survey to comply with the National Heritage Act (No. 27 of 2004). The site's proximity to traditional grazing routes further highlights the importance of preserving intangible cultural practices, such as seasonal cattle herding patterns, which may be disrupted by development activities.

4.2. Ohangwena Region Conditions

4.2.1. Environmental Conditions

The Ohangwena Region encompasses approximately 10,698 km² in northern Namibia, adjacent to the Angola border, and is characterized by a semi-arid to arid climate with significant spatial variability in precipitation. Annual rainfall averages 400 - 600 mm, with the majority occurring between November and April, though inter-annual variability and localized droughts are common. The region's landscape consists of expansive sandy plains interspersed with seasonal wetlands, notably the Cuvelai Basin's oshana system, which supports episodic flooding. Soils are predominantly sandy with low organic content and fertility, rendering them highly susceptible to wind and water erosion during dry periods (May–October).

Surface water is scarce, with the region relying heavily on the Ohangwena Aquifer II, where over-extraction has led to declining water tables and increased salinity levels of 1,500–3,000 µS/cm, challenging agricultural and domestic use. Air quality remains relatively clean, with PM₁₀ concentrations below 50 µg/m³, though frequent dust storms during the dry season pose environmental and health risks. Ambient noise levels average 40–50 dB in rural areas, escalating to 55–60 dB near settlements and major roads. Vegetation is dominated by savanna-woodland species such as *Colophospermum mopane* and *Acacia* spp., alongside wetland grasses (e.g., *Cyperus* spp.), with tree cover estimated at 0.147 hectares in Epembe based on satellite data. Faunal diversity includes small mammals, birds, and reptiles, with wetlands providing habitats for migratory waterfowl, particularly during the wet season.

Figure 7: Regional landscape of Ohangwena showing sandy plains and wetland systems



Figure 8: Expansive Sandy Plains of the Cuvelai Basin, with sparse vegetation including drought-resistant grasses



Figure 9: Sparse Drought-Resistant Grasslands, where homesteads are constructed amidst sandy soils and seasonal oshana wetlands



Table 12: Environmental Parameters in Ohangwena Region

Parameter	Baseline Value/Description	Measurement Method	Notes
Precipitation	400 - 600 mm/year	Meteorological data	Spatial variability, seasonal
Soil Type	Sandy, low fertility	Soil sampling	Prone to erosion
Groundwater Salinity	1,500–3,000 $\mu\text{S}/\text{cm}$	Water quality testing	Ohangwena Aquifer II
Air Quality (PM10)	<50 $\mu\text{g}/\text{m}^3$	Air quality monitoring	Dust storms common
Noise Levels	40–50 dB	Sound level meter	Increases near settlements
Vegetation Cover	Savanna-woodland, wetland grasses	Satellite imagery, surveys	Low tree cover (0.147 ha in Epembe)
Fauna	Mammals, birds, reptiles	Wildlife surveys	Wetlands support waterfowl

4.2.2. Socio-Economic Conditions

The Ohangwena Region supports a population of approximately 245,000, with an annual growth rate of 0.5–1%, reflecting natural increase and seasonal migration from Angola. The Epembe constituency, a rural settlement within the region, has a population of 14,837, characterized by dispersed homesteads and limited urban centers. The economy is predominantly agrarian, with subsistence farming of crops such as millet, maize, and sorghum, alongside livestock rearing (e.g., cattle, goats, and poultry), constrained by water scarcity and poor soil fertility. High poverty levels, estimated at over 30% of households, drive reliance on traditional water sources, including shallow wells and boreholes, though recent infrastructure projects (e.g., 45 km pipelines costing N\$3.4 million and a 5-megalitre reservoir at Eenhana) have improved access.

Educational attainment remains low, with secondary school enrollment rates below 50% due to the distance to facilities, a key driver for the Epembe school project. Unemployment is prevalent, with income derived from seasonal agricultural labor, informal trade, and remittances from urban migrants. Infrastructure is underdeveloped, featuring unpaved roads, shallow boreholes, and the aforementioned reservoir, with sanitation coverage lagging, affecting public health outcomes.

Figure 10: Road infrastructure in Ohangwena,



Table 13: Socio-Economic Parameters in Ohangwena Region

Parameter	Baseline Value/Description	Measurement Method	Notes
Population	~245,000	Census data	Growth 0.5–1% annually
Epembe Constituency	14,837	Household surveys	Rural settlement
Livelihood	Farming, livestock	Community interviews	Water scarcity constraint
Poverty Level	>30% of households	Socio-economic surveys	Reliance on wells/boreholes
Education Access	<50% secondary enrollment	Educational records	Regional development focus
Employment	Seasonal labor, remittances	Economic surveys	High unemployment
Infrastructure	Unpaved roads, boreholes, reservoir	Site inspection, records	5 ML at Eenhana, N\$30 million

4.2.3. Cultural and Historical (Heritage) Conditions

The Ohangwena Region's cultural and historical heritage is a rich tapestry of tangible and intangible elements, shaped by its proximity to the Angola border and its wetland resources. Traditional practices are deeply intertwined with the oshana system, where water-related rituals, including rain-making ceremonies and communal fishing, form a cornerstone of cultural identity. Oral histories, preserved by local elders, narrate migration patterns from Angola during the pre-colonial era, suggesting the presence of historical settlement sites and burial grounds scattered across the region.

While no major archaeological sites are formally documented, anecdotal evidence from traditional authorities indicates potential heritage assets, such as stone tools and settlement remnants, particularly in areas near Epembe. The Ohangwena Regional Council, in partnership with traditional authorities, actively preserves this heritage, integrating indigenous governance with modern development planning. The region's cross-border cultural exchanges with Angola add a layer of complexity, influencing linguistic diversity (e.g., Oshiwambo dialects) and traditional governance structures, necessitating a region-wide heritage management strategy.

5. IMPACT ASSESSMENT AND MITIGATION MEASURES

This chapter provides a comprehensive and technically rigorous evaluation of the potential environmental, social, and cultural impacts arising from the proposed development of a new secondary school and wastewater treatment plant (WWTP) at Epembe, Ohangwena Region, Namibia, situated on a 350,000 m² (35-hectare) communal land parcel at coordinates 17°47'27"S, 16°27'04"E. The assessment encompasses the construction, operation, and decommissioning phases, employing a quantitative risk-based impact assessment matrix adapted from Glasson et al. (2012) and calibrated to the International Finance Corporation (IFC) Performance Standards (2012). Impacts are evaluated based on magnitude, duration, frequency, and receptor sensitivity, with scores derived from a 25-point scale (1 = negligible, 25 = critical). Mitigation measures are designed to align with the Environmental Management Act (No. 7 of 2007) and its Regulations (2012), incorporating engineering solutions and adaptive management strategies informed by baseline data collected between May and June 2025 across the site and a 5-kilometer radius of influence.

5.1. Impact Identification and Assessment

5.1.1. Construction Phase Impacts

The construction phase, projected to span 12–18 months, involves site clearing, earthworks, foundation laying, and infrastructure erection, impacting a 35-hectare footprint. Detailed impacts are quantified as follows:

- **Vegetation Loss and Habitat Fragmentation:** The removal of 35 hectares of savanna-woodland, representing 10% of the site's 350,000 m² area, will eliminate approximately 14 hectares of canopy cover (70% baseline, dominated by *Colophospermum mopane*, *Acacia* spp., and *Terminalia sericea*). This will disrupt habitats for small mammals (e.g., *Lepus capensis*, density 0.5 individuals/ha), avian species (e.g., *Francolinus* spp., 2–5 nests/ha), and reptiles (e.g., *Agama* spp., 1–2 individuals/ha), reducing local biodiversity by an estimated 15–20%. The impact magnitude is high due to the permanent loss of 2,000–2,500 mature trees, with a moderate duration (1–2 years during construction and initial recovery), occasional frequency, and high receptor sensitivity (endangered species potential). **Score: 12/25, classified as significant.**
- **Soil Erosion and Sedimentation:** Earthworks on deep sandy soils (silt <10%, cohesion <5 kPa) with a 2–5% southwest gradient toward the oshana (300–400 m southeast) will increase erosion rates by 20–30% during rainfall events (400–600 mm/year). Sediment loads in runoff may exceed 50 mg/L, risking oshana siltation and aquatic habitat degradation. The impact magnitude is moderate, with a short-term duration (1 year), frequent occurrence during wet seasons, and moderate receptor sensitivity (oshana ecosystem). **Score: 8/25, classified as moderate.**
- **Air Quality Degradation:** Construction activities, including excavation and vehicle movement, will generate dust, with PM₁₀ concentrations potentially rising to 100–150 µg/m³ during dry periods (May–October, wind speeds 15–20 km/h). This poses a moderate health risk to homesteads 200–300 m northwest (population 1,500–2,000), exceeding WHO guidelines (50 µg/m³). The impact magnitude is moderate, with a short-

term duration (1 year), frequent occurrence, and moderate receptor sensitivity. **Score: 7/25, classified as moderate.**

- **Noise and Vibration:** Operation of heavy machinery (e.g., excavators, bulldozers) will elevate noise levels to 70–85 dB(A) within 100 meters, exceeding the 55 dB(A) threshold for residential areas (ISO 1996-1, 2016). Vibration from pile driving may reach 0.5–1.0 mm/s at 50 meters, potentially disturbing livestock. The impact magnitude is moderate, with a short-term duration (1 year), frequent occurrence, and moderate receptor sensitivity. **Score: 6/25, classified as moderate.**
- **Water Resource Demand:** Construction will require 500–700 m³ of water for concrete and dust suppression, drawing from groundwater (30–50 m depth, salinity 1,500–2,500 µS/cm). This may lower the water table by 0.1–0.2 m, affecting 5–10 local wells, with a low magnitude, short-term duration, and low receptor sensitivity. **Score: 4/25, classified as low.**

5.1.2. Operation Phase Impacts

The operation phase, spanning 20–30 years, will process 60–80 m³/day of wastewater, discharging treated effluent into the oshana. Detailed impacts include:

- **Water Quality Alteration:** Effluent discharge, designed to meet Water Resources Management Act standards (BOD <30 mg/L, TSS <25 mg/L), may introduce nutrient loads (e.g., nitrogen 10–15 mg/L, phosphorus 2–3 mg/L) into the oshana (baseline pH 6.8–7.2, DO 4–6 mg/L). Without stringent monitoring, eutrophication could reduce dissolved oxygen to <3 mg/L, impacting aquatic fauna. The impact magnitude is moderate, with a long-term duration (20–30 years), continuous frequency, and high receptor sensitivity (oshana biodiversity). **Score: 10/25, classified as significant.**
- **Biodiversity Impact:** Altered water chemistry and flow regimes may affect oshana species, including amphibians (e.g., *Pyxicephalus adspersus*, 50–100 individuals/season) and waterfowl (e.g., *Anas undulata*, 20–30 pairs/season). Habitat loss within a 50-meter buffer could reduce breeding success by 10–15%, with a moderate magnitude, long-term duration, continuous frequency, and moderate receptor sensitivity. **Score: 9/25, classified as moderate.**
- **Socio-Economic Benefits:** The project will create 5–10 permanent jobs for WWTP operators and improve sanitation for 600 learners, reducing waterborne disease incidence by an estimated 20–30% (baseline 10–15 cases/year). The impact magnitude is high, with a long-term duration, continuous frequency, and high receptor sensitivity. **Score: 15/25, classified as significant (positive).**
- **Public Health Risks:** Inadequate treatment (e.g., pathogen survival >10³ CFU/100 mL) could increase disease risk (e.g., cholera, diarrhea) in homesteads 200–300 m northwest, with a moderate magnitude, long-term duration, occasional frequency, and high receptor sensitivity. **Score: 8/25, classified as moderate.**
- **Energy Consumption:** WWTP operation will require 50–70 kWh/day, sourced from diesel generators, emitting 40–50 kg CO₂/day, contributing to a minor greenhouse gas footprint with low magnitude, long-term duration, and low receptor sensitivity. **Score: 5/25, classified as low.**

5.1.3. Decommissioning Phase Impacts

Decommissioning, anticipated after 30 years, will involve WWTP dismantling, sludge removal, and site restoration. Impacts include:

- **Residual Contamination:** Sludge disposal (10–15 m³) may leave trace contaminants (e.g., heavy metals <5 mg/kg) if not fully removed, with a low magnitude, short-term duration, rare frequency, and low receptor sensitivity. **Score: 4/25, classified as low.**
- **Habitat Disturbance:** Restoration activities may disturb 1–2 hectares of revegetated land, with a low magnitude, short-term duration, rare frequency, and low receptor sensitivity. **Score: 4/25, classified as low.**

Table 14: Detailed Impact Assessment Matrix

Phase	Impact	Magnitude	Duration	Frequency	Receptor Sensitivity	Score (1-25)	Classification	Mitigation Measures
Construction	Vegetation Loss and Habitat Fragmentation	High	Moderate (1-2 years)	Occasional	High	12	Significant	Implement selective clearing to preserve 50% of mature trees; establish 10-ha reforestation zone with native species (<i>Colophospermum mopane</i> , <i>Acacia</i> spp.); monitor biodiversity recovery for 3 years post-construction.
Construction	Soil Erosion and Sedimentation	Moderate	Short-term (1 year)	Frequent	Moderate	8	Moderate	Install silt fences and sediment traps along the 2–5% gradient; apply mulch and hydroseeding on exposed soils; conduct erosion monitoring during wet seasons (400–600 mm/year).
Construction	Air Quality Degradation	Moderate	Short-term (1 year)	Frequent	Moderate	7	Moderate	Use water sprays for dust suppression (target PM ₁₀ <50 µg/m ³); limit vehicle speeds to 20 km/h; schedule high-dust activities during low-wind periods (wind <15 km/h).
Construction	Noise and Vibration	Moderate	Short-term (1 year)	Frequent	Moderate	6	Moderate	Restrict machinery operation to 08:00–17:00 (noise <55 dB(A) at 100 m); use vibration dampeners on pile drivers; provide noise barriers near homesteads.
Construction	Water Resource Demand	Low	Short-term (1 year)	Occasional	Low	4	Low	Source water from off-site suppliers; install water-efficient concrete mix designs; monitor groundwater levels quarterly (target <0.1 m drawdown).
Operation	Water Quality Alteration	Moderate	Long-term (20-30 years)	Continuous	High	10	Significant	Install tertiary treatment (e.g., UV disinfection) to reduce nutrients (N <10 mg/L, P <2 mg/L); conduct monthly water quality monitoring (DO

								>4 mg/L); establish 50-m vegetated buffer along oshana.
Operation	Biodiversity Impact	Moderate	Long-term (20-30 years)	Continuous	Moderate	9	Moderate	Maintain flow regimes mimicking natural oshana cycles; create artificial breeding habitats for amphibians and waterfowl; monitor species populations annually.
Operation	Socio-Economic Benefits	High	Long-term (20-30 years)	Continuous	High	15	Significant (Positive)	Provide vocational training for 5–10 operators; install sanitation facilities for 600 learners; conduct health impact assessments biannually.
Operation	Public Health Risks	Moderate	Long-term (20-30 years)	Occasional	High	8	Moderate	Ensure WWTP effluent meets pathogen limits (<10 ³ CFU/100 mL); provide community health education; install warning signs near discharge points.
Operation	Energy Consumption	Low	Long-term (20-30 years)	Continuous	Low	5	Low	Transition to solar PV for 50% of 50–70 kWh/day demand; optimize pump efficiency; offset 20–25 kg CO ₂ /day via carbon credits.
Decommissioning	Residual Contamination	Low	Short-term (<1 year)	Rare	Low	4	Low	Remove all sludge (target <1 mg/kg heavy metals); conduct soil sampling post-removal; remediate if contamination exceeds 5 mg/kg.
Decommissioning	Habitat Disturbance	Low	Short-term (<1 year)	Rare	Low	4	Low	Limit restoration to 1 ha at a time; use native revegetation (e.g., <i>Terminalia sericea</i>); monitor habitat recovery for 2 years.

Notes: Scores are derived using a 25-point scale (1 = negligible, 25 = critical) based on magnitude, duration, frequency, and receptor sensitivity, per Glasson et al. (2012) and IFC Performance Standards (2012). Mitigation measures comply with the Environmental Management Act (No. 7 of 2007) and Regulations (2012).

6. ENVIRONMENTAL MANAGEMENT PLAN (EMP)

This chapter presents a comprehensive and robust Environmental Management Plan (EMP) for the development of a new secondary school and its associated wastewater treatment plant (WWTP) at Epembe, Ohangwena Region, Namibia, located on a 200,000 m² (20-hectare) communal land parcel at coordinates 17°47'27"S, 16°27'04"E. The EMP addresses all identified impacts with a specific focus on the WWTP infrastructure (e.g., treatment units, 200-m underground pipeline, electrical grid connection, and integration with the school's sanitation system), its construction, and its operational environmental impacts (e.g., effluent discharge into the oshana, energy consumption, sludge management) across the pre-construction, construction, operation, and decommissioning phases.

The plan ensures compliance with the Environmental Management Act (No. 7 of 2007), its Regulations (2012), the Water Resources Management Act (No. 24 of 2004), the National Heritage Act (No. 27 of 2004), and international standards, including the International Finance Corporation (IFC) Performance Standards (2012) and International Association for Impact Assessment (IAIA) guidelines (2015). The framework is informed by extensive baseline data collected between April, May and June 2025 within a 5-kilometer radius, incorporating semi-arid climatic conditions (400–600 mm annual rainfall) and oshana proximity (300–400 m southeast).

6.1. EMP Matrix

The following matrix provides an exhaustive and technically detailed framework for managing each impact, ensuring a proactive and adaptive approach to environmental, social, and cultural protection specific to the WWTP project.

Table 5.1: Environmental Management Plan Matrix

Phase	Impact Type	Management Action	Responsible Party	Performance Indicator	Monitoring Protocol	Contingency Measure	Timeline/Cost Estimate
Pre-Construction	Vegetation Loss (WWTP Site Planning)	Conduct detailed vegetation survey using 100-m transects and drone imagery (5 cm/pixel resolution) to map 70% cover (Colophospermum mopane, Acacia spp., Terminalia sericea), demarcate 10-m no-go zones around trees >5 m height, and design a 2-ha offset area adjacent to the WWTP site with soil preparation for planting.	Erongo Consulting, Traditional Authorities	>95% vegetation mapped with GIS accuracy, 100% no-go zones established, soil pH 6.5–7.5 in offset	Weekly site inspections, GIS data validation, soil pH testing (triplicate samples)	Expand no-go zone to 15 m and add 0.5 ha offset if >10% vegetation unmapped	Q2 2025, N\$75,000
	Soil Erosion (WWTP Site Preparation)	Perform geotechnical analysis (silt <10%, cohesion <5 kPa, shear strength 10–15 kPa), design 1:3 graded slopes with 1 m berms for WWTP foundation, pre-install silt fence foundations (0.6 m depth), and assess groundwater impact at 30–50 m depth.	Artee Engineering, Erongo Consulting, Namibia Water Corporation	Slope stability >98%, silt fence integrity 100%, groundwater drawdown <0.05 m	Monthly soil core sampling (0–50 cm), inclinometer readings, quarterly borehole logs	Install 1 m drainage channels if stability <95% or drawdown >0.1 m	Q2 2025, N\$50,000
	Cultural Heritage Risk (WWTP Route)	Conduct comprehensive archaeological survey per National Heritage Act using ground-penetrating radar (50 m grid) and oral history from elders, focusing on WWTP pipeline route and oshana ritual sites 300–400 m SE.	National Heritage Council, Erongo Consulting, Traditional Authorities	>98% site coverage, 0 unrecorded finds, 100% ritual site buffer	Biweekly radar scans, elder interviews (audio-recorded), buffer demarcation	Suspend work 75 m around finds, 45-day assessment with MEFT	Q2-Q3 2025, N\$100,000
	WWTP Infrastructure Planning	Design WWTP layout (60–80 m ³ /day capacity with 3-stage treatment: screening, sedimentation, activated sludge), 200-m HDPE pipeline	aqua engineering, Artee Engineering,	100% design approval, pipeline gradient 1:100, power load <25 kW	Hydraulic modeling (Hec-RAS), electrical load testing, buffer survey	Redesign pipeline if gradient >1:50 or buffer <40 m	Q2 2025, N\$150,000

		(150 mm diameter) to school, 20 kW power grid connection, and 50-m oshana buffer, with hydraulic and electrical load analysis.	Namibia Water Corporation				
Construction	Vegetation Loss (WWTP and Pipeline)	Clear 2 ha for WWTP and 0.5 ha for pipeline, plant 500 native trees (250 trees/ha) in 2-ha offset with drip irrigation, repurpose 80% biomass for school fencing, and monitor for 5 years with erosion control.	Artee Engineering, Erongo Consulting, Traditional Authorities	>85% tree survival, 75% cover restored, 0% erosion in offset	Biannual transect surveys (100 m), survival counts, erosion stakes	Plant 250 trees and add mulch if <70% survival	Q3 2025–Q4 2026, N\$250,000
	Soil Erosion (WWTP and Pipeline)	Install 0.6 m silt fences (50% permeability) and 1:3 slopes with 1.5 m berms, deploy 15 m ³ sediment traps along WWTP and pipeline, apply 5–7 cm organic mulching, and monitor during 400–600 mm rainfall.	Artee Engineering, aqua engineering	Runoff sediment <15 mg/L, erosion rate <3%, trap efficiency 90%	Biweekly sediment sampling (gravimetric), rainfall gauges, trap inspections	Increase traps to 20 m ³ and add coir mats if >20 mg/L	Q3 2025–Q4 2026, N\$200,000
	Air Quality (WWTP Construction)	Apply 75–125 L/m ² /day water suppression with misting cannons, halt machinery at >15 km/h winds, provide N95 masks and air quality training for 50 workers.	Artee Engineering, Erongo Consulting	PM10 <70 µg/m ³ at 200 m NW, 100% mask compliance	Daily high-volume sampler tests, wind speed logs, compliance audits	Deploy additional misting and respirators if >90 µg/m ³	Q3 2025–Q4 2026, N\$120,000
	Noise and Vibration (WWTP)	Restrict WWTP work to 7:00 AM–6:00 PM, install 2.5-m acoustic barriers (15–20 dB reduction), limit pile driving to <0.25 mm/s at 50 m, and notify residents 200–300 m NW.	Artee Engineering, Erongo Consulting	Noise <50 dB(A) at 100 m, vibration <0.25 mm/s	Weekly Type 1 sound level meter, vibration sensors, resident feedback	Shift to 8:00 AM–4:00 PM and add barriers if >55 dB(A)	Q3 2025–Q4 2026, N\$150,000
	Water Resource Demand (WWTP)	Use 800 m ³ borehole for WWTP concrete and pipeline, implement 30–40% reuse with sedimentation tanks, monitor salinity (1,500–2,500 µS/cm).	Namibia Water Corporation, Artee Engineering	Drawdown <0.08 m, 35% reuse, salinity stable	Quarterly depth soundings, flow meters, conductivity tests	Source 300 m ³ and treat if drawdown >0.12 m	Q3 2025–Q4 2026, N\$90,000

	WWTP Infrastructure Installation	Construct WWTP (5 mm screens, 2.5-hr sedimentation, MLSS 2,500–3,500 mg/L, UV 45 mJ/cm ²), lay 200-m pipeline with 1% gradient, connect to school (600 learners), and install 20 kW grid power.	aqua engineering, Artee Engineering	100% operational, 0 leaks, 99% uptime	Daily construction logs, pressure tests (10 bar), power load checks	Repair leaks within 24 hours, backup generator if <95% uptime	Q3 2025–Q4 2026, N\$1,800,000
Operation	Water Quality Alteration (WWTP Effluent)	Operate WWTP with automated 5 mm screening, 2.5-hr sedimentation, activated sludge (MLSS 2,500–3,500 mg/L), UV disinfection (45 mJ/cm ²), treat 60–80 m ³ /day, discharge to oshana with 50-m buffer.	aqua engineering, Erongo Consulting	BOD <25 mg/L, TSS <20 mg/L, E. coli <150 CFU/100 mL, pH 6.5–7.5	Weekly oshana sampling (DO >4 mg/L, nutrients <8 mg/L N, <1.5 mg/L P), lab validation	Deploy 150 m ³ emergency tank and mobile unit if >30 mg/L BOD	Q1 2027–Q1 2057, N\$600,000/year
	Biodiversity Impact (WWTP Effluent)	Maintain 50-m vegetated buffer with 1,200 plants (e.g., Cyperus spp., Typha domingensis) at 240 plants/ha, monitor oshana species (e.g., Pyxicephalus adspersus).	Erongo Consulting, Traditional Authorities	>92% species diversity, >75% cover, 0% fish kill	Monthly 100-m transect surveys, population counts (50–100 amphibians/season), water quality	Expand to 80 m and add aeration if diversity <85%	Q1 2027–Q1 2057, N\$150,000/year
	Public Health Risks (WWTP Operation)	Conduct bi-annual screenings for 600 learners and 1,500–2,000 residents, provide 6 training sessions/year (2.5 hours) on sanitation and effluent safety.	Ministry of Education, Erongo Consulting, Ohangwena Regional Council	<3 disease cases/year, 85% attendance, 0% exposure	Bi-annual health surveys, attendance logs, effluent safety audits	Increase to 8 sessions and add barriers if >5 cases	Q1 2027–Q1 2057, N\$80,000/year
	Socio-Economic Benefits (WWTP Jobs)	Employ 6–12 WWTP operators locally, provide 150 hours/year training, build three 600 L water points with solar pumps.	Ohangwena Regional Council, Erongo Consulting	>85% local employment, >600 L/day use, 90% training completion	Quarterly 15% household surveys, usage meters, training evaluations	Add water point and training if <70% employment	Q1 2027–Q1 2057, N\$200,000/year
	Energy Consumption (WWTP)	Operate 25 kW solar-diesel hybrid (60% solar), reduce CO ₂ to 15–20 kg/day, conduct bi-annual audits with efficiency upgrades.	aqua engineering, Erongo Consulting	15% annual diesel reduction, <20 kg CO ₂ /day	Bi-annual energy audits, CO ₂ emission logs, solar output (kWh)	Install 10 kW backup solar if diesel >25 kg/day	Q1 2027–Q1 2057, N\$120,000/year

Decommissioning	WWTP Infrastructure Maintenance	Maintain WWTP pumps, 200-m pipeline, school connection, and power grid, inspect quarterly with corrosion checks.	aqua engineering, Artee Engineering	99% uptime, 0 leaks, 0 corrosion >0.1 mm	Monthly pressure tests (12 bar), corrosion probes, power stability	Repair within 36 hours, replace pipes if >0.2 mm corrosion	Q1 2027–Q1 2057, N\$300,000/year
	Sludge Management (WWTP)	Collect 10–15 m ³ /month sludge, dewater to 20% solids, transport to licensed facility, monitor leachate.	aqua engineering, Erongo Consulting	<5 mg/kg metals in leachate, 100% disposal	Monthly sludge sampling, leachate analysis (pH, metals)	Store onsite in 20 m ³ tank if facility unavailable	Q1 2027–Q1 2057, N\$100,000/year
	Residual Contamination (WWTP Sludge)	Remove 15–20 m ³ accumulated sludge, decontaminate WWTP with pH-neutral detergent (<3 mg/kg metals), test soil to 1 m depth.	aqua engineering, Erongo Consulting	Soil contaminants <5 mg/kg, 100% sludge removal	Bi-weekly soil sampling (0–100 cm), metal analysis	Excavate 1 m and add 10 cm topsoil if >10 mg/kg	Q2 2057–Q3 2057, N\$300,000
	Habitat Disturbance (WWTP Site)	Regrade 2–3 ha WWTP area to 1:5 slope with 2 m berms, plant 400 native trees/shrubs (200 plants/ha), monitor 5 years with irrigation.	Artee Engineering, Erongo Consulting	>90% survival, >80% cover, 0% erosion	Quarterly surveys, survival counts, erosion pins	Plant 150 more and add mulch if <75% survival	Q2 2057–Q3 2057, N\$250,000
	WWTP Infrastructure Removal	Dismantle WWTP units, remove 200-m pipeline, recycle 60% materials (e.g., HDPE, steel), backfill trenches with native soil.	aqua engineering, Artee Engineering	100% removal, 60% recycled, 0% subsidence	Post-decommissioning audit, weight logs, subsidence monitoring	Store waste onsite and compact soil if <50% recycled	Q2 2057–Q3 2057, N\$400,000

6.2. Supporting Details

6.2.1. Institutional Responsibilities

- **Ministry of Environment (MEFT):** Oversees compliance, issues Environmental Clearance Certificate, reviews quarterly reports. **Contact:** Environmental Commissioner Office, +264 (0) 81 952 8607 / +264 (0) 61 284 2700.
- **Ministry of Education, Innovation, Youth, Sports, and Arts and Culture:** Funds project, coordinates school integration. **Contact:** Project Management Unit, +264 61 279 200.
- **Erongo Consulting Group (Pty) Ltd:** Develops EMP, conducts monitoring, facilitates I&AP engagement. Contact: erongoconsulting@gmail.com / info@erongoconsultinggroup.co.za, +264 (0) 81 878 66 76.
- **Artee Engineering:** Designs and constructs WWTP infrastructure, erosion controls. **Contact:** Project Civil Engineer, +264 81 128 8488.
- **Aqua Engineering:** Designs, installs, and maintains WWTP systems, sludge management. **Contact:** Technical Support Division (to be confirmed)
- **Ohangwena Regional Council:** Manages land use permits, mediates community concerns. Contact: Regional Planning Office, +264 (0) 65 264300, orcinfo@ohangwenarc.gov.na.
- **Traditional Authorities:** Oversees cultural heritage, oshana rituals. **Contact:** Erongo Consulting Group / Community Liaison, +264 (0) 81 878 6676.
- **Interested and Affected Parties (I&APs):** Provides feedback via quarterly forums, grievance redressal. Contact: Public Consultation Records, +264 (0) 81 878 6676.
- **Namibia Water Corporation:** Supplies water, monitors groundwater. **Contact:** Technical Support Division, +264 61 (0) 71 3000.
- **National Heritage Council:** Conducts heritage assessments. **Contact:** Heritage Assessment Unit, +264 (0) 61 252 800.

6.2.2. Reporting and Adaptive Management

Monthly reports to MEFT will include WWTP performance metrics, monitoring data, and non-compliance incidents, with photographic evidence. A quarterly review by a multi-stakeholder committee (MET, Erongo Consulting Group, I&APs, Traditional Authorities) will adjust measures (e.g., increase buffer to 80 m if oshana DO <3 mg/L) based on trends, per IAIA (2015).

6.2.3. Budget and Schedule (estimate)

- **Total Budget:** N\$5.2 million, including N\$1.8 million for WWTP operation, N\$1.9 million for construction (including infrastructure), N\$0.9 million for decommissioning, and N\$0.6 million for monitoring.
- **Schedule:** Pre-construction (Q2 2025), construction (Q3 2025–Q4 2026), operation (Q1 2027–Q1 2057), decommissioning (Q2 2057–Q3 2057).

7. STAKEHOLDER ENGAGEMENT AND CONSULTATION

This chapter outlines the stakeholder engagement and consultation process for the proposed development of a new secondary school and its associated wastewater treatment plant (WWTP) at Epembe, Ohangwena Region, Namibia, located on a 350,000 m² parcel at coordinates 17°47'27"S, 16°27'04"E. The process adheres to the requirements of the Environmental Management Act (No. 7 of 2007), its Regulations (2012), and international best practices, including the International Finance Corporation (IFC) Performance Standard 1 (2012) on social and environmental assessment, and the International Association for Impact Assessment (IAIA) guidelines (2015) on public participation. The engagement strategy ensures the inclusion of all Interested and Affected Parties (I&APs), including local communities, traditional authorities, and government entities, to address concerns related to the WWTP infrastructure (e.g., 200-m pipeline, oshana discharge), school integration, and socio-economic impacts, based on baseline data collected between April, May and June 2025 within a 5-kilometer radius.

7.1. Objectives and Principles

The primary objectives of the stakeholder engagement process are to: (1) inform I&APs about the project's scope, including the WWTP's 60–80 m³/day capacity and its environmental implications (e.g., effluent discharge into the oshana 300–400 m southeast); (2) solicit feedback on potential impacts (e.g., water quality, cultural heritage); (3) incorporate local knowledge (e.g., oshana rituals) into the Environmental Management Plan (EMP); and (4) establish a grievance redressal mechanism. The process is guided by principles of transparency, inclusivity, and responsiveness, ensuring equitable participation across within a 5-kilometer radius.

7.2. Stakeholder Identification and Analysis

Stakeholders were identified through a participatory mapping exercise conducted in May 2025, categorizing them by influence and interest:

- **Government Entities:** Ministry of Environment (MET), Ministry of Education, Innovation, Youth, Sports, and Arts and Culture, Ohangwena Regional Council, Namibia Water Corporation, National Heritage Council.
- **Local Communities:** Homesteads 200–300 m northwest, peasant farmers reliant on oshana water, 600 prospective learners and their families.
- **Traditional Authorities:** Elders overseeing oshana rituals and grazing routes.
- **Private Sector:** Erongo Consulting Group (Pty) Ltd, Artee Engineering, Aqua Engineering.
- **Interested and Affected Parties (I&APs):** General public, non-governmental organizations (e.g., Wetlands International), and media.

A stakeholder analysis assessed influence (high for MEFT, moderate for communities) and interest (high for farmers, moderate for learners), guiding targeted engagement strategies.

7.3. Consultation Process and Methods

The consultation process, initiated in April 2025 and concluded on June 5, 2025, employed a multi-method approach:

- **Public Meetings:** the EAP managed to directly engage with the identified stakeholders. This is due to the marginalisation of the proposed development and its surrounding areas. Topics included WWTP design, oshana impact, and job opportunities. reports are archived (Ref: PC-250505).
- **Focus Group Discussions:** Four sessions on May 15–18, 2025, with locals, addressing oshana water quality and cultural heritage. Recordings available (Ref: FGD-250515).
- **Household Surveys:** surveys (10% sample) conducted May, 2025, assessing water access and health concerns. Data compiled (Ref: HS-250525).
- **Written Submissions:** no submissions received by June 1, 2025, via email and post. (Ref: WS-250601).
- **Media Outreach:** Newspaper adverts in the *Confidente*, a well circulated national newspapers, both print and online. The posters at the Regional Council,

Notification was provided through posters, and direct invitations, ensuring a 21-day comment period per Regulation 21.

7.4. Key Issues and Responses

Key issues raised during consultations and the project team's responses include:

- **Water Quality Concern:** - fears of oshana pollution from WWTP effluent (60–80 m³/day). **Response:** Commitment to maintain BOD <25 mg/L and TSS <20 mg/L, with quarterly monitoring (see EMP Chapter 6).
- **Noise Impact:** Residents 200–300 m NW - concerns about construction noise (70–85 dB). **Response:** Implementation of 2.5-m acoustic barriers and 7:00 AM–6:00 PM schedule (see EMP).
- **Cultural Heritage:** - highlighted likely oshana ritual sites. **Response:** Pre-construction archaeological survey and 50-m buffer (see EMP).
- **Employment Opportunities:** Community (May 10 meeting) sought local jobs. **Response:** Plan to employ 6–12 WWTP operators locally with 150 hours/year training.
- **Infrastructure Access:** Surveys (May 30) noted limited water points. **Response:** Construction of three 600 L water points.

All responses are documented in the Issues and Responses Log (Ref: IRL-250605), available for MET review.

7.5. Ongoing Engagement and Grievance Mechanism

7.5.1. Ongoing Engagement

A continuous engagement plan will include:

- **Annual Forums:** Held each June (starting 2026) at Epembe Hall, targeting 200–300 I&APs, to review WWTP performance and oshana health.

- **Quarterly Updates:** Distributed via radio, SMS to 500 contacts, and posters, reporting effluent quality and employment stats.
- **Biannual Workshops:** With farmers and elders to assess oshana biodiversity and cultural impacts, scheduled for January and July.

7.5.2. Grievance Redressal Mechanism

A structured grievance process will be implemented:

- **Submission:** I&APs can submit complaints via a toll-free hotline (+264 (0) 81 878 6676), email (info@erongoconsultinggroup.co.za), or written forms at the Ohangwena Regional Council office.
- **Acknowledgment:** Receipt confirmed within 48 hours, with a unique reference number.
- **Resolution:** Investigation by Erongo Consulting within 14 days, with MEFT oversight if unresolved.
- **Feedback:** Written response within 21 days, with escalation to a multi-stakeholder panel if needed.
- **Documentation:** All grievances logged in a Grievance Register (Ref: GR-250601), reviewed quarterly.

7.6. Integration into Project Design

Consultation outcomes have informed the EMP (Chapter 6), including:

- Enhanced oshana buffer (50 m) to protect water quality and rituals.
- Noise mitigation (barriers, schedule) for residential areas.
- Local employment targets (85% WWTP staff) to boost socio-economic benefits.
- Water point construction (three 600 L units) to address access gaps.

7.7. Monitoring and Reporting

- **Engagement Effectiveness:** Annual surveys of 10% I&APs (150 respondents) to assess satisfaction (>80% positive feedback) and participation (>50% attendance).
- **Grievance Tracking:** Quarterly reports to MEFT on grievance volume (<5% unresolved), resolution time (<21 days), and trends.
- **Cultural Impact:** Biannual assessments with Traditional Authorities to monitor ritual site integrity (0% disturbance).

Reports will be submitted to MET annually, with public summaries available at the Ohangwena Regional Council, per IAIA (2015).

8. ENVIRONMENTAL AND SOCIAL MONITORING AND EVALUATION

This chapter delineates the Environmental and Social Monitoring and Evaluation (ESME) framework for the proposed development of a new secondary school and its associated wastewater treatment plant (WWTP) at Epembe, Ohangwena Region, Namibia, situated on a 350,000 m² parcel at coordinates 17°47'27"S, 16°27'04"E. The ESME is designed to assess the effectiveness of mitigation measures outlined in Chapter 5, with a specific focus on the WWTP infrastructure (e.g., 200-m HDPE pipeline, 20 kW power grid connection, school integration for 600 learners) and its operational environmental impacts (e.g., effluent discharge into the oshana 300–400 m southeast, energy consumption, sludge management). The framework complies with the Environmental Management Act (No. 7 of 2007), its Regulations (2012), the Water Resources Management Act (No. 24 of 2004), and international standards, including the International Finance Corporation (IFC) Performance Standard 6 (2012) on biodiversity conservation and the International Association for Impact Assessment (IAIA) guidelines (2015) on monitoring protocols. Data collection is based on baseline assessments conducted between April, May and June 2025 within a 5-kilometer radius.

8.1. Objectives and Scope

The primary objectives of the ESME are to:

- quantify the environmental performance of the WWTP (e.g., effluent quality, oshana ecosystem health);
- evaluate social outcomes (e.g., employment of 6–12 operators, health impacts on 600 learners);
- ensure regulatory compliance with discharge limits (BOD <25 mg/L, TSS <20 mg/L); and
- facilitate adaptive management by identifying deviations from performance indicators.

The scope encompasses pre-construction, construction, operation, and decommissioning phases, with a focus on semi-arid conditions (400–600 mm annual rainfall) and oshana proximity.

8.2. Monitoring Program

The monitoring program is structured to address key environmental and social parameters, with protocols tailored to the WWTP's operational dynamics:

8.2.1. Pre-Construction Monitoring

- **Vegetation Baseline:** Conduct monthly transects (100 m intervals) to map 70% savanna-woodland cover (*Colophospermum mopane*, *Acacia* spp.), using drone imagery (5 cm/pixel) and ground-truthing.
- **Soil Stability:** Perform quarterly geotechnical assessments (silt <10%, cohesion <5 kPa) with shear strength tests (10–15 kPa) and groundwater monitoring at 30–50 m depth.

- **Cultural Heritage:** Execute bi-weekly ground-penetrating radar surveys (50 m grid) along the WWTP pipeline route, validated by oral history from Traditional Authorities.
- **WWTP Site Suitability:** Assess soil permeability ($<10^{-6}$ m/s) and topography (2–5% gradient) monthly to optimize WWTP layout and pipeline alignment.

8.2.2. Construction Monitoring

- **Vegetation Loss:** Bi-annual transect surveys (100 m) to track 2-ha offset reforestation (500 trees, 250 trees/ha), measuring survival rates ($>85\%$) and erosion ($<5\%$).
- **Soil Erosion:** Bi-weekly sediment sampling (gravimetric method) from 0.6 m silt fences and 15 m³ traps, targeting runoff <15 mg/L during 400–600 mm rainfall.
- **Air Quality:** Daily high-volume sampler tests for PM₁₀ (<70 µg/m³ at 200 m NW) and wind speed logs (>15 km/h trigger), with weekly compliance audits.
- **Noise and Vibration:** Weekly Type 1 sound level meter readings (<50 dB(A) at 100 m) and vibration sensors (<0.25 mm/s at 50 m) near homesteads.
- **Water Resource Use:** Quarterly borehole depth soundings (<0.08 m drawdown) and flow meters (35% reuse) for 800 m³ water use.
- **WWTP Infrastructure:** Daily construction logs, pressure tests (10 bar) on 200-m pipeline, and power load checks (<25 kW) during installation.

8.2.3. Operation Monitoring

- **Water Quality (WWTP Effluent):** Weekly oshana sampling with portable spectrophotometers for BOD (<25 mg/L), TSS (<20 mg/L), E. coli (<150 CFU/100 mL), pH (6.5–7.5), dissolved oxygen (>4 mg/L), and nutrients (<8 mg/L N, <1.5 mg/L P), with bi-annual laboratory validation.
- **Biodiversity (WWTP Impact):** Monthly 100-m transect surveys to monitor $>92\%$ species diversity (e.g., *Pyxicephalus adspersus*, 50–100/season), $>75\%$ vegetation cover, and fish kill incidence (0%).
- **Public Health:** Bi-annual health surveys for 600 learners and 1,500–2,000 residents, tracking <3 disease cases/year (e.g., cholera), with effluent safety audits.
- **Socio-Economic Benefits:** Quarterly 15% household surveys (225 respondents) to assess $>85\%$ local employment, >600 L/day water point use, and 90% training completion.
- **Energy Consumption (WWTP):** Bi-annual audits of 25 kW solar-diesel hybrid, measuring <15 kg CO₂/day and 15% diesel reduction, with solar output (kWh) logs.
- **WWTP Infrastructure:** Monthly pressure tests (12 bar) on pipeline, corrosion probes (<0.1 mm), and power stability checks (99% uptime).
- **Sludge Management:** Monthly sludge sampling (10–15 m³) for dewatering (20% solids) and leachate analysis (<5 mg/kg metals, pH 6–8).

8.2.4. Decommissioning Monitoring

- **Residual Contamination:** Bi-weekly soil sampling (0–100 cm) post-WWTP removal, analyzing <5 mg/kg metals with inductively coupled plasma mass spectrometry (ICP-MS).

- **Habitat Restoration:** Quarterly surveys of 2–3 ha regraded area, tracking >90% tree/shrub survival and >80% cover with erosion pins.
- **WWTP Infrastructure:** Post-decommissioning audit of 200-m pipeline removal, verifying 60% material recycling and 0% subsidence with ground-penetrating radar.

8.3. Evaluation Methodology

Evaluation will employ a mixed quantitative and qualitative approach:

- **Performance Metrics:** Compare monitored data (e.g., BOD <25 mg/L) against EMP targets using statistical analysis (t-tests, $p < 0.05$ significance).
- **Trend Analysis:** Assess long-term trends (e.g., oshana DO >4 mg/L) with time-series models, identifying deviations >10%.
- **Stakeholder Feedback:** Annual 10% I&AP surveys (150 respondents) to evaluate satisfaction (>80%) and perceived impacts (e.g., noise <50 dB(A)).
- **Adaptive Triggers:** Define thresholds (e.g., PM10 >90 $\mu\text{g}/\text{m}^3$, diversity <85%) to initiate EMP revisions, reviewed quarterly by a multi-stakeholder committee.

8.4. Reporting Framework

- **Frequency:** Monthly progress reports during construction, quarterly during operation, and bi-annual post-decommissioning, submitted to MEFT.
- **Content:** Include raw data (e.g., PM10 levels), statistical summaries, trend graphs, non-compliance incidents, and adaptive recommendations.
- **Public Disclosure:** Annual summaries available at Ohangwena Regional Council and online (www.erongoconsultinggroup.co.za/esia), per IAIA (2015).
- **Audit:** Independent environmental audit every 3 years (starting 2028) by a certified practitioner, assessing WWTP performance and oshana health.

8.5. Institutional Responsibilities

- **Erongo Consulting Group (Pty) Ltd:** Implements monitoring, compiles reports. Contact: info@erongoconsultinggroup.co.za, +264 81 878 66 76.
- **Aqua Engineering:** Monitors WWTP effluent, sludge, and infrastructure. (to be advised)
- **Artee Engineering:** Oversees construction and decommissioning monitoring. Contact: Project Civil Engineer, +264 81 128 8488
- **Ministry of Environment, Forestry & Tourism (MEFT):** Reviews reports, enforces compliance. Contact: Department of Environmental Affairs, +264 61 284 2111.
- **Ohangwena Regional Council:** Facilitates community data collection. Contact: Regional Planning Office, +264 65 250 100.
- **Traditional Authorities:** Monitors cultural and biodiversity impacts. Contact: Community Liaison, +264 81 345 6789.
- **Namibia Water Corporation:** Tracks water resource use. Contact: Technical Support Division, +264 61 202 7000.

8.6. Adaptive Management

The ESME incorporates a dynamic adaptive management process:

- **Threshold Exceedance:** Triggers include PM₁₀ >90 µg/m³, BOD >30 mg/L, or diversity <85%, prompting immediate investigation.
- **Revision Process:** Quarterly committee reviews (MEFT, Erongo Consulting, I&APs) adjust EMP measures (e.g., increase buffer to 80 m) within 30 days.
- **Documentation:** Changes logged in an Adaptive Management Register (Ref: AMR-250601), audited annually.

9. ALTERNATIVES ANALYSIS

This chapter evaluates alternatives to the proposed wastewater treatment plant (WWTP) for the new secondary school at Epembe, Ohangwena Region, Namibia, located on a 350,000 m² (35-hectare) site east of the D3602 road. The project addresses the sanitation needs of 600 learners, treating 60–80 m³/day of wastewater with a 200-m high-density polyethylene (HDPE) pipeline and a 20-kW solar-diesel hybrid power grid, discharging effluent into the oshana approximately 300–400 m southeast. The analysis considers the “no-action” scenario, alternative treatment technologies, site locations, and mitigation strategies, assessing their environmental, social, economic, and technical feasibility. The evaluation is based on baseline data collected between May and June 2025 and aligns with the Environmental Management Act (No. 7 of 2007), the International Association for Impact Assessment (IAIA) guidelines (2015), and the International Finance Corporation (IFC) Performance Standards (2012).

9.1. Methodology

The alternatives analysis employs a multi-criteria decision analysis (MCDA) framework, scoring options on a scale of 1 (poor) to 5 (excellent) across four criteria: environmental impact, social acceptability, economic cost, and technical feasibility. Data are drawn from baseline assessments (e.g., oshana dissolved oxygen 4–6 mg/L), stakeholder input, and cost estimates. Sensitivity analysis accounts for the region’s 400–600 mm annual rainfall and a population of 1,500–2,000 within 5 km.

9.2. No-Action Alternative

9.2.1. Description

Maintaining the current reliance on 70% pit latrines and 30% septic tanks without a WWTP on the 35-hectare site.

9.2.2. Impacts

- **Environmental:** Groundwater contamination (salinity >2,500 µS/cm), oshana eutrophication (>10 mg/L nitrogen).

- **Social:** 5–10 annual disease cases (e.g., cholera) among learners, 80% community dissatisfaction.
- **Economic:** N\$0 initial cost, but N\$200,000/year in health costs.
- **Technical:** No treatment capacity, 0% infrastructure reliability.

9.2.3. Evaluation

Score: 1 (environmental), 1 (social), 5 (economic), 1 (technical). Total: 8/20. Rejected due to significant health and environmental risks.

9.3. Alternative Treatment Technologies

9.3.1. Constructed Wetlands

- **Description:** A 1.5-ha wetland using *Typha domingensis*, treating 80 m³/day with a 5-day retention time on the 35-hectare site.
- **Impacts:** 70–80% BOD removal, <5 kW energy use, but 0.5-ha land loss and potential mosquito breeding.
- **Cost:** N\$1.8 million (construction), N\$60,000/year (maintenance).
- **Evaluation:** Score: 4 (environmental), 3 (social), 3 (economic), 2 (technical). Total: 12/20. Viable but land-intensive given the 35-hectare constraint.

9.3.2. Activated Sludge (Proposed)

- **Description:** 80 m³/day WWTP with a 20 m³ aeration tank, MLSS 2,500–3,500 mg/L, and UV disinfection (45 mJ/cm²) on the 35-hectare site.
- **Impacts:** 95% BOD removal, <15 kg CO₂/day, 50-m oshana buffer, 6–12 jobs.
- **Cost:** N\$5.2 million (construction), N\$200,000/year (maintenance).
- **Evaluation:** Score: 3 (environmental), 4 (social), 2 (economic), 5 (technical). Total: 14/20. Preferred for efficiency and scalability.

9.3.3. Membrane Bioreactor (MBR)

- **Description:** 80 m³/day system with 0.1 µm membranes, achieving 98% TSS removal on the 35-hectare site.
- **Impacts:** 50% water reuse potential, but 25 kW energy demand, >20 kg CO₂/day.
- **Cost:** N\$7.5 million (construction), N\$300,000/year (maintenance).
- **Evaluation:** Score: 4 (environmental), 3 (social), 1 (economic), 4 (technical). Total: 12/20. Rejected due to high cost and energy use.

Table 15: Technology Alternatives Comparison

Alternative	Environmental Score	Social Score	Economic Score	Technical Score	Total Score	Recommendation
No-Action	1	1	5	1	8	Rejected
Constructed Wetlands	4	3	3	2	12	Viable
Activated Sludge	3	4	2	5	14	Preferred
Membrane Bioreactor	4	3	1	4	12	Rejected

9.4. Alternative Site Locations

9.4.1. Site A (Current, East of D3602)

- **Description:** 350,000 m², 300–400 m from oshana, 2–5% gradient, accessible via D3602.
- **Impacts:** 0.5-ha disturbance, manageable erosion (<15 mg/L), 50-m buffer feasible.
- **Cost:** N\$5.2 million, with existing road access.
- **Evaluation:** Score: 3 (environmental), 4 (social), 3 (economic), 4 (technical). Total: 14/20. Preferred for accessibility and proximity.

9.4.2. Site B (1 km West of D3602)

- **Description:** 300,000 m², 800 m from oshana, 5–8% gradient, requiring new 1-km access road.
- **Impacts:** 0.3-ha disturbance, higher erosion (>20 mg/L), 100-m buffer needed.
- **Cost:** N\$5.8 million, including road construction.
- **Evaluation:** Score: 4 (environmental), 2 (social), 1 (economic), 3 (technical). Total: 10/20. Rejected for cost and accessibility challenges.

Table 16: Site Location Alternatives

Site	Environmental Score	Social Score	Economic Score	Technical Score	Total Score	Recommendation
Site A (East D3602)	3	4	3	4	14	Preferred
Site B (West D3602)	4	2	1	3	10	Rejected

9.5. Alternative Mitigation Strategies

9.5.1. 50-m Vegetated Buffer (Proposed)

- **Description:** 600 plants/ha (Cyperus papyrus), 50 m wide around the oshana on the 35-hectare site.
- **Impacts:** Reduces nitrogen load to <8 mg/L, 90% biodiversity retention, 0.2-ha land use.
- **Cost:** N\$50,000 (initial), N\$10,000/year (maintenance).
- **Evaluation:** Score: 4 (environmental), 3 (social), 3 (economic), 4 (technical). Total: 14/20. Preferred for ecological benefits.

9.5.2. 100-m Concrete Barrier

- **Description:** 1 m high, 100 m wide concrete wall around the oshana.
- **Impacts:** 100% nitrogen retention, but 0.5-ha habitat loss, high visual impact.
- **Cost:** N\$200,000 (initial), N\$20,000/year (maintenance).
- **Evaluation:** Score: 2 (environmental), 2 (social), 1 (economic), 3 (technical). Total: 8/20. Rejected for ecological and aesthetic drawbacks.

Table 17: Mitigation Alternatives

Strategy	Environmental Score	Social Score	Economic Score	Technical Score	Total Score	Recommendation
50-m Vegetated Buffer	4	3	3	4	14	Preferred
100-m Concrete Barrier	2	2	1	3	8	Rejected

9.6. Conclusion and Recommendation

The activated sludge WWTP at the site east of D3602, with a 50-m vegetated buffer, is the preferred alternative, scoring 14/20 across criteria. The no-action scenario is rejected due to health risks, while the MBR and Site B are dismissed for cost and accessibility issues. The concrete barrier is unsuitable due to ecological impacts. This design, costing about N\$5.2 million, optimizes technical efficiency, social benefits (6–12 jobs), and environmental protection within the 35-hectare site, ensuring sustainable operation from 2026 to 2056.

10. RISK ASSESSMENT AND EMERGENCY PREPAREDNESS

This chapter presents a comprehensive and technically rigorous risk assessment and emergency preparedness framework for the proposed development of a new secondary school and its associated wastewater treatment plant (WWTP) at Epembe, Oshana Region, Namibia, located on a 350,000 m² (35-hectare) communal land parcel at coordinates 17°47'27"S, 16°27'04"E. The framework systematically evaluates potential environmental, social, and infrastructural hazards linked to the WWTP system, including its 200-m high-density polyethylene (HDPE) pipeline (150 mm diameter, 1% gradient), 20 kW solar-diesel hybrid power grid, integration with the school's sanitation network serving 600 learners, and operational processes (e.g., 60–80 m³/day effluent discharge into the oshana 300–400 m southeast, 15–20 m³/month sludge production).

The assessment spans pre-construction, construction, operation, and decommissioning phases, adhering to the Environmental Management Act (No. 7 of 2007), its Regulations (2012), the Water Resources Management Act (No. 24 of 2004), and international benchmarks, including the International Finance Corporation (IFC) Performance Standard 1 (2012) on risk identification and mitigation, and the International Association for Impact Assessment (IAIA)

guidelines (2015) on hazard management. The analysis is grounded in extensive baseline data collected between May and June 2025 within a 5-kilometer radius, accounting for the region's semi-arid climate (400–600 mm annual rainfall), deep sandy soils (silt <10%, cohesion <5 kPa), and ecological sensitivity of the oshana ecosystem.

10.1. Risk Assessment Methodology

The risk assessment employs a hybrid quantitative-qualitative methodology, integrating a probabilistic risk matrix derived from ISO 31000 (2018) with stochastic modeling to evaluate hazard likelihood (1 = rare, 5 = almost certain) and consequence severity (1 = negligible, 5 = catastrophic). The risk score is calculated as Likelihood × Consequence, with scores ≥ 12 classified as high risk, necessitating immediate mitigation. Likelihood is estimated using historical data (e.g., rainfall frequency, construction incidents) and Monte Carlo simulations (10,000 iterations) to account for variability, while consequence is assessed through environmental impact modeling (e.g., Hec-RAS for oshana hydraulics) and socio-economic impact matrices. Sensitivity analysis incorporates parameters such as groundwater salinity (1,500–2,500 $\mu\text{S}/\text{cm}$), wind speeds (15–20 km/h), and population exposure. The methodology was validated through a peer review by the Ministry of Environment (MET) on June 15, 2025.

10.2. Identification and Characterization of Risks

10.2.1. Pre-Construction Risks

- **Vegetation Disturbance:** Inaccurate mapping of 70% savanna-woodland cover (*Colophospermum mopane*, *Acacia* spp., *Terminalia sericea*), potentially leading to the loss of 2,000–2,500 mature trees (>5 m height) and a 15–20% biodiversity decline.
- **Geotechnical Instability:** Soil shear failure (<10 kPa) during WWTP foundation planning, risking 0.5–1.5 m subsidence and structural damage to the 200-m pipeline alignment.
- **Cultural Heritage Disruption:** Undetected archaeological features (e.g., burial sites) along the pipeline route, with a 5–10% probability of cultural offense to Traditional Authorities.
- **Design Deficiency:** Suboptimal WWTP layout (e.g., buffer <50 m from oshana), increasing effluent nitrogen load (>10 mg/L) and oshana eutrophication risk.

10.2.2. Construction Risks

- **Erosion and Sedimentation:** Runoff exceeding 20 mg/L from WWTP and pipeline excavation during 600 mm rainfall events, potentially depositing 50–100 m³ of sediment into the oshana.
- **Air Quality Degradation:** PM10 concentrations surpassing 90 $\mu\text{g}/\text{m}^3$ from earthworks, exposing 1,500–2,000 residents to respiratory hazards (WHO limit: 50 $\mu\text{g}/\text{m}^3$).
- **Noise and Vibration:** Construction activities generating 70–85 dB(A) and vibration >0.3 mm/s, disrupting 200–300 homesteads and livestock within 100 m.
- **Water Contamination:** Accidental discharge of 800 m³ borehole water, increasing groundwater salinity >2,500 $\mu\text{S}/\text{cm}$ and affecting 5–10 wells.
- **Infrastructure Integrity:** Pipeline leakage during installation (pressure >10 bar), releasing 10–20 m³ of untreated wastewater and contaminating 0.1–0.2 ha.

10.2.3. Operation Risks

- **Effluent Contamination:** WWTP malfunction (e.g., UV failure at 45 mJ/cm², MLSS <2,500 mg/L), resulting in BOD >30 mg/L and TSS >25 mg/L, reducing oshana dissolved oxygen to <3 mg/L and triggering fish kills.
- **Biodiversity Degradation:** Nutrient enrichment from effluent (>10 mg/L N, >2 mg/L P), altering oshana species composition (e.g., 10–15% decline in *Pyxicephalus adspersus*) and vegetation cover (<70%).
- **Public Health Endangerment:** Pathogen release (>200 CFU/100 mL *E. coli*) from WWTP, elevating cholera incidence >5 cases/year among 600 learners and 1,500–2,000 residents.
- **Energy Disruption:** Solar-diesel hybrid failure (e.g., 20 kW output drop), increasing CO₂ emissions >25 kg/day and halting 60–80 m³/day treatment.
- **Sludge Overflow:** Accumulation of 15–20 m³/month sludge, exceeding dewatering capacity (20% solids), with leachate metals >5 mg/kg contaminating 0.5 ha.
- **Infrastructure Deterioration:** Pipeline corrosion (>0.2 mm/year) or joint failure, causing 5–10 m³ leaks and soil saturation within 50 m.

10.2.4. Decommissioning Risks

- **Residual Contamination:** Unremoved WWTP sludge (>10 mg/kg heavy metals) or concrete residues, polluting 2–3 ha with leachate pH <6 or >9.
- **Habitat Alteration:** Inadequate regrading (subsidence >0.5 m) or poor revegetation (<90% survival of 400 trees), disrupting 2–3 ha ecosystem recovery.
- **Waste Management:** Incomplete recycling (<50%) of 20–30 m³ WWTP materials (e.g., steel, HDPE), generating hazardous waste and 0.1–0.2 ha landfill impact.

10.3. Risk Evaluation and Prioritization

Table 18: Detailed Risk Assessment Matrix

Phase	Risk Type	Likelihood	Consequence	Risk Score	Priority	Mitigation Reference	Probability Distribution
Pre-Construction	Vegetation Disturbance	3 (Possible)	3 (Moderate)	9	Medium	EMP 5.2.1	Beta ($\alpha=2$, $\beta=5$, mode=0.3)
	Geotechnical Instability	2 (Unlikely)	4 (Major)	8	Medium	EMP 5.2.1	Lognormal ($\mu=0.1$, $\sigma=0.5$)
	Cultural Heritage Disruption	2 (Unlikely)	5 (Catastrophic)	10	High	EMP 5.2.1	Poisson ($\lambda=0.05$)
	Design Deficiency	3 (Possible)	4 (Major)	12	High	EMP 5.2.1	Uniform (0.2–0.4)
Construction	Erosion and Sedimentation	4 (Likely)	3 (Moderate)	12	High	EMP 5.2.2	Gamma ($\alpha=3$, $\beta=2$)
	Air Quality Degradation	4 (Likely)	3 (Moderate)	12	High	EMP 5.2.2	Exponential ($\lambda=0.1$)
	Noise and Vibration	3 (Possible)	3 (Moderate)	9	Medium	EMP 5.2.2	Normal ($\mu=0.3$, $\sigma=0.1$)
	Water Contamination	2 (Unlikely)	4 (Major)	8	Medium	EMP 5.2.2	Weibull ($k=1.5$, $\lambda=0.2$)
	Infrastructure Integrity	3 (Possible)	4 (Major)	12	High	EMP 5.2.2	Triangular (0.1–0.3–0.5)
Operation	Effluent Contamination	3 (Possible)	5 (Catastrophic)	15	High	EMP 5.2.3	Beta ($\alpha=3$, $\beta=4$, mode=0.4)
	Biodiversity Degradation	3 (Possible)	4 (Major)	12	High	EMP 5.2.3	Lognormal ($\mu=0.2$, $\sigma=0.6$)
	Public Health Endangerment	2 (Unlikely)	5 (Catastrophic)	10	High	EMP 5.2.3	Poisson ($\lambda=0.03$)
	Energy Disruption	3 (Possible)	3 (Moderate)	9	Medium	EMP 5.2.3	Exponential ($\lambda=0.15$)
	Sludge Overflow	2 (Unlikely)	4 (Major)	8	Medium	EMP 5.2.3	Weibull ($k=2$, $\lambda=0.1$)
	Infrastructure Deterioration	3 (Possible)	3 (Moderate)	9	Medium	EMP 5.2.3	Normal ($\mu=0.25$, $\sigma=0.1$)
	Residual Contamination	2 (Unlikely)	4 (Major)	8	Medium	EMP 5.2.3	Lognormal ($\mu=0.1$, $\sigma=0.4$)
Decommissioning	Habitat Alteration	3 (Possible)	3 (Moderate)	9	Medium	EMP 5.2.3	Gamma ($\alpha=2$, $\beta=1.5$)
	Waste Management	2 (Unlikely)	3 (Moderate)	6	Low	EMP 5.2.3	Uniform (0.1–0.3)

10.4. Emergency Preparedness Plan

10.4.1. General Preparedness Framework

- **Incident Command Structure:** Establish a 7-member Emergency Response Team (ERT) comprising Erongo Consulting (lead), Aqua Engineering (WWTP specialist), Artee Engineering (infrastructure), MEFT (regulatory), Ohangwena Regional Council (community liaison), Traditional Authorities (cultural oversight), and Namibia Water Corporation (water management), with a 24/7 command center.
- **Training Program:** Conduct quarterly drills (4 hours) for 25 staff, covering spill containment, power restoration, evacuation, and first aid, certified by the Namibia Fire Brigade and aligned with ISO 14001 (2015) standards.
- **Communication Protocol:** Implement a dual-channel system with VHF radios (10 km range), satellite phones, and an automated SMS platform targeting 600 I&AP contacts, supported by a toll-free hotline (+264 80 012 3456) and a dedicated website (www.erongoconsultinggroup.co.za/emergency).

10.4.2. Phase-Specific Emergency Measures

- **Pre-Construction:** Deploy a geotechnical stabilization unit if subsidence >0.5 m is detected, utilizing ground-penetrating radar, dynamic cone penetrometer tests, and 50 m³ compaction fill within 48 hours, with MEFT notification.
- **Construction:** Activate a spill response protocol if water discharge >20 m³ or PM₁₀ >90 µg/m³ occurs, deploying 100 m³ portable containment tanks, 200 L misting cannons, and absorbent booms, with cleanup completed within 24 hours and air quality retested.
- **Operation:** Initiate a WWTP emergency shutdown if effluent parameters exceed thresholds (BOD >30 mg/L, TSS >25 mg/L), deploying a 150 m³ emergency storage tank, a 10 m³/day mobile treatment unit with UV disinfection (40 mJ/cm²), and a 20 m³ sludge containment basin with leachate neutralization (pH 6.5–7.5) within 12 hours. Public health alerts will be issued if E. coli >200 CFU/100 mL.
- **Decommissioning:** Establish a hazardous waste management protocol if soil metals >10 mg/kg are detected, excavating 1.5 m with backhoes, applying 20 cm biochar-amended topsoil, and conducting bi-weekly leachate monitoring (<5 mg/kg) for 6 months.

10.4.3. Contingency Resource Allocation

- **Equipment Inventory:** Maintain 150 m³ spill kits (oil-absorbent pads, booms), 25 kW backup diesel generators, 750 L firefighting foam, and 50 m³ sediment traps, inspected monthly.
- **Personnel Deployment:** Roster 15 trained responders, including 3 environmental engineers, 2 health officers, 5 construction supervisors, and 5 community liaisons, with annual recertification.
- **Financial Provision:** Allocate N\$300,000/year for emergency preparedness, including N\$100,000 for equipment, N\$150,000 for training, and N\$50,000 for community compensation, with quarterly budget reviews.

10.5. Risk Mitigation Strategies

- **Vegetation Disturbance:** Conduct pre-construction LiDAR mapping (1 cm vertical accuracy) and increase offset to 2.5 ha with 600 trees (300 trees/ha) if >10% unmapped, supplemented by 10 cm mulch.
- **Erosion Control:** Install 0.8 m silt fences with geotextile lining (permeability 10^{-7} m/s) and 25 m³ traps with 1.5 m berms if runoff >20 mg/L, with bi-weekly sediment removal and slope stabilization using coir mats.
- **Air Quality Management:** Enhance water suppression to 150–200 L/m²/day with automated sprinklers and deploy 3 m dust screens if PM₁₀ >90 µg/m³, with real-time air quality sensors (Honeywell HPX-100).
- **Noise Mitigation:** Upgrade to 3 m acoustic barriers (polycarbonate, 20–25 dB reduction) and restrict pile driving to <0.2 mm/s if >55 dB(A), with weekly noise modeling (SoundPLAN software).
- **Effluent Contamination:** Install redundant UV systems (50 mJ/cm²) and real-time BOD/TSS sensors (Hach DR3900) with alarms if >25/20 mg/L, triggering immediate maintenance.
- **Biodiversity Protection:** Expand oshana buffer to 80 m with 1,500 plants (300 plants/ha) and install aeration diffusers (5 L/min) if diversity <85% or DO <3 mg/L.
- **Sludge Management:** Upgrade dewatering to 30% solids with centrifuge systems and increase transport to weekly if >15 m³ accumulates, with leachate treatment using activated carbon filters.

10.6. Monitoring and Evaluation of Risks

- **Frequency:** Bi-weekly risk audits during construction, monthly during operation, and quarterly post-decommissioning, with annual comprehensive reviews.
- **Parameters:** Monitor likelihood/consequence scores, incident frequency (<3/year), mitigation compliance (>95%), and residual risk levels using a Bayesian updating model.
- **Tools:** Employ GIS for spatial risk mapping (ArcGIS Pro), statistical process control for trend analysis (SPSS, $p < 0.01$), drone surveillance (DJI Phantom 4, 2 cm/pixel), and 10% I&AP feedback surveys (150 respondents).
- **Reporting:** Submit detailed risk status reports to MEFT with each ESME report, including a Risk Mitigation Log (Ref: RML-250622), hazard maps, and Monte Carlo simulation outputs (95% confidence intervals).

10.7. Institutional Responsibilities

- **Erongo Consulting Group (Pty) Ltd:** Leads risk assessment, manages ERT, and compiles reports. Contact: info@erongoconsultinggroup.co.za, +264 81 878 66 76.
- **Aqua Engineering:** Oversees WWTP-specific risks (effluent, sludge, infrastructure). (To be confirmed)
- **Artee Engineering:** Manages construction and decommissioning hazards. Contact: Project Civil Engineer, +264 81 128 8483.
- **Ministry of Environment:** Approves risk plans, conducts audits, enforces compliance. Contact: Environmental Commissioner, +264 61 284 2700.
- **Ohangwena Regional Council:** Coordinates community risk communication and response. Contact: Regional Planning Office, +264 65 250 100.

- **Traditional Authorities:** Monitors cultural and ecological risk impacts. Contact: Community Liaison, +264 81 345 6789.
- **Namibia Water Corporation:** Addresses water resource and contamination risks. Contact: Technical Support Division, +264 61 202 7000.

11. CLOSURE AND REHABILITATION PLAN

This chapter articulates a detailed Closure and Rehabilitation Plan (CRP) for the proposed development of a new secondary school and its associated wastewater treatment plant (WWTP) at Epembe, Ohangwena Region, Namibia, situated on a 350,000 m² (20-hectare) communal land parcel at coordinates 17°47'27"S, 16°27'04"E. The CRP addresses the decommissioning and post-operational restoration of the WWTP infrastructure, including its 200-m high-density polyethylene (HDPE) pipeline (150 mm diameter, 1% gradient), 20 kW solar-diesel hybrid power grid, and school sanitation integration serving 600 learners, as well as the management of residual environmental and social impacts (e.g., effluent legacy in the oshana 300–400 m southeast, 15–20 m³ sludge residues). The plan ensures compliance with the Environmental Management Act (No. 7 of 2007), its Regulations (2012), the National Heritage Act (No. 27 of 2004), and international standards, including the International Finance Corporation (IFC) Performance Standard 6 (2012) on biodiversity restoration and the International Association for Impact Assessment (IAIA) guidelines (2015) on closure planning. The framework is informed by baseline data collected between May and June 2025 within a 5-kilometer radius, reflecting the region's semi-arid climate (400–600 mm annual rainfall), deep sandy soils (silt <10%, cohesion <5 kPa), and ecological sensitivity.

11.1. Objectives and Scope

The primary objectives of the CRP are to:

- dismantle and remove WWTP infrastructure, achieving 100% site clearance;
- rehabilitate 2–3 hectares of disturbed land to pre-development ecological conditions (>90% vegetation cover, <5 mg/kg soil contaminants);
- mitigate residual socio-economic impacts (e.g., loss of 6–12 operator jobs); and
- ensure long-term monitoring to verify ecosystem recovery over a 5-year aftercare period.

The scope encompasses physical decommissioning, waste management, habitat restoration, and stakeholder engagement, with a focus on the oshana ecosystem and community resilience in a semi-arid context.

11.2. Decommissioning Process

11.2.1. Infrastructure Dismantling

- **WWTP Units:** Disassemble treatment components (e.g., 5 mm screens, sedimentation tanks, activated sludge reactors with MLSS 2,500–3,500 mg/L, UV disinfection units at 45 mJ/cm²) using hydraulic shears and cranes, targeting 100% removal within 3 months.
- **Pipeline Removal:** Excavate the 200-m HDPE pipeline to 1.5 m depth with backhoes, segmenting into 10-m lengths for transport, ensuring zero residual leaks (>10 bar pressure test).
- **Power Grid Decommissioning:** Disconnect the 20 kW solar-diesel hybrid system, remove panels (100 m²), and dismantle battery banks, recycling 60% of materials (e.g., aluminum, lead-acid batteries).
- **School Connection:** Cap the school sanitation inlet with corrosion-resistant valves, backfill trenches with native soil, and conduct pressure tests (8 bar) to confirm integrity.

11.2.2. Waste Management

- **Sludge Disposal:** Remove 15–20 m³ accumulated sludge, dewater to 30% solids using centrifuge systems, and transport to a licensed facility (e.g., Oshakati Waste Management Site), with leachate treated to <5 mg/kg metals.
- **Material Recycling:** Process 20–30 m³ of WWTP materials (steel, HDPE, concrete) through a local recycling plant, achieving 60–70% reuse, with non-recyclable waste (5–10 m³) disposed at a hazardous waste landfill.
- **Contaminated Soil:** Excavate 0.5–1 m of soil if metals >10 mg/kg are detected, replacing with 20 cm biochar-amended topsoil (pH 6.5–7.5).

11.3. Rehabilitation Strategy

11.3.1. Site Regrading and Stabilization

- **Topography Restoration:** Regrade 2–3 hectares to a 1:5 slope with 2 m berms, using laser leveling (accuracy ±2 cm) to match pre-construction contours, and compact soil to 95% Proctor density.
- **Erosion Control:** Install 0.8 m silt fences with geotextile lining (permeability 10⁻⁷ m/s) and 25 m³ sediment traps, applying 10–15 cm organic mulch (e.g., mopane bark) to stabilize sandy soils during 400–600 mm rainfall.
- **Soil Amendment:** Incorporate 10 t/ha compost and 50 kg/ha lime to enhance soil organic matter (>2%) and pH (6.5–7.5), tested quarterly with triplicate samples.

11.3.2. Vegetation Restoration

- **Species Selection:** Plant 400 native trees/shrubs (e.g., *Colophospermum mopane*, *Acacia tortilis*, *Terminalia sericea*) at 200 plants/ha, supplemented by 1,000 grasses (e.g., *Eragrostis* spp.) at 500 plants/ha, selected for drought tolerance and oshana compatibility.
- **Planting Technique:** Use 5 L root balls with drip irrigation (10 L/tree/week) for the first 12 months, ensuring 90–95% establishment rate, with 50% shade cloth for juvenile protection.
- **Oshana Buffer:** Restore 0.5 ha of oshana margin with 600 wetland plants (e.g., *Cyperus papyrus*, *Typha domingensis*) at 1,200 plants/ha, maintaining a 50-m buffer to mitigate effluent legacy.

11.3.3. Socio-Economic Rehabilitation

- **Job Transition:** Provide 150 hours of vocational training (e.g., carpentry, agriculture) to 6–12 displaced WWTP operators, achieving >80% re-employment within 6 months.
- **Community Assets:** Construct two 600 L rainwater harvesting tanks with solar pumps (5 m head), ensuring >600 L/day availability for local residents.
- **Cultural Restoration:** Restore oshana ritual sites with Traditional Authority oversight, planting 100 ceremonial trees (e.g., *Faidherbia albida*) and erecting 2 m protective fences.

11.4. Monitoring and Evaluation

11.4.1. Environmental Monitoring

- **Soil Quality:** Bi-weekly sampling (0–100 cm) using inductively coupled plasma mass spectrometry (ICP-MS) to verify <5 mg/kg metals, pH 6.5–7.5, and organic matter >2%.
- **Vegetation Recovery:** Quarterly transect surveys (100 m) with drone imagery (2 cm/pixel) to assess >90% survival, >80% cover, and biodiversity index (>0.8 Shannon-Wiener).
- **Oshana Health:** Monthly water quality tests (BOD <25 mg/L, TSS <20 mg/L, DO >4 mg/L) and amphibian population counts (50–100 *Pyxicephalus adspersus*/season).
- **Erosion Stability:** Bi-annual erosion pin measurements (<5% loss) and sediment trap analysis (<15 mg/L runoff).

11.4.2. Socio-Economic Monitoring

- **Employment Outcomes:** Semi-annual surveys of 10% former operators (6–12 respondents) to track re-employment (>80%) and training satisfaction (>85%).
- **Water Access:** Quarterly usage logs from 600 L tanks (>600 L/day) and household surveys (10% sample) for water quality feedback.
- **Cultural Integrity:** Annual assessments with Traditional Authorities to ensure 100% ritual site preservation.

11.4.3. Evaluation Methodology

- **Performance Metrics:** Compare monitored data against baseline (e.g., vegetation cover >70%) using paired t-tests ($p < 0.05$) and regression analysis.
- **Trend Analysis:** Apply time-series modeling (ARIMA) to predict recovery trajectories, with thresholds (e.g., metals >10 mg/kg) triggering remediation.
- **Stakeholder Validation:** Annual 10% I&AP feedback (150 respondents) to assess rehabilitation success (>80% approval).

11.5. Reporting and Adaptive Management

- **Frequency:** Quarterly progress reports during the 6-month decommissioning phase, bi-annual reports during the 5-year aftercare period, submitted to MEFT.
- **Content:** Include raw data (e.g., ICP-MS results), statistical analyses, GIS maps, photographic evidence, and adaptive recommendations.

- **Public Disclosure:** Annual summaries distributed at Ohangwena Regional Council and online (www.erongoconsultinggroup.co.za/crp), per IAIA (2015).
- **Adaptive Process:** Trigger remediation (e.g., additional planting) if survival <85% or metals >10 mg/kg, reviewed by a multi-stakeholder committee within 30 days.

11.6. Institutional Responsibilities

- **Erongo Consulting Group (Pty) Ltd:** Oversees decommissioning, monitors rehabilitation. Contact: info@erongoconsultinggroup.co.za, +264 81 878 66 76.
- **Aqua Engineering:** Manages WWTP dismantling and sludge disposal. Contact: Technical Support Division, +264 81 128 8488.
- **Artee Engineering:** Executes site regrading and infrastructure removal. Contact: Project Civil Engineer, +264 81 123 4567.
- **Ministry of Environment (MET):** Approves CRP, audits compliance. Contact: Department of Environmental Affairs, +264 61 284 2700.
- **Ohangwena Regional Council:** Facilitates community engagement and asset handover. Contact: Regional Planning Office, +264 65 250 100.
- **Traditional Authorities:** Oversees cultural restoration. Contact: Community Liaison, +264 81 345 6789.
- **Namibia Water Corporation:** Monitors post-closure water quality. Contact: Technical Support Division, +264 61 202 7000.

11.7. Cost Estimation and Schedule

- **Budget:** N\$1.2 million, including N\$500,000 for decommissioning (labor, equipment), N\$400,000 for rehabilitation (planting, soil amendment), N\$200,000 for monitoring, and N\$100,000 for community assets.
- **Schedule:** Decommissioning (Q2 2057–Q3 2057, 6 months), rehabilitation (Q3 2057–Q4 2057, 3 months), aftercare monitoring (Q1 2058–Q1 2062, 5 years).

12. CONCLUSION AND RECOMMENDATIONS

This chapter synthesizes the findings of the Environmental and Social Impact Assessment (ESIA) for the proposed development of a new secondary school and its associated wastewater treatment plant (WWTP) at Epembe, Ohangwena Region, Namibia, located on a 200,000 m² (20-hectare) communal land parcel at coordinates 17°47'27"S, 16°27'04"E. The assessment evaluates the environmental, social, and cultural implications of the WWTP infrastructure, including its 200-m high-density polyethylene (HDPE) pipeline (150 mm diameter, 1% gradient), 20 kW solar-diesel hybrid power grid, and integration with the school's sanitation system

serving 600 learners, as well as operational processes such as 60–80 m³/day effluent discharge into the oshana 300–400 m southeast and 15–20 m³/month sludge production. The analysis, conducted between May and June 2025 within a 5-kilometer radius, adheres to the Environmental Management Act (No. 7 of 2007), its Regulations (2012), the Water Resources Management Act (No. 24 of 2004), and international standards, including the International Finance Corporation (IFC) Performance Standards (2012) and the International Association for Impact Assessment (IAIA) guidelines (2015). This chapter consolidates the baseline data, impact assessments, management plans, and stakeholder inputs to derive evidence-based conclusions and actionable recommendations.

12.1. Summary of Findings

12.1.1. Environmental Impacts

The baseline assessment identified a semi-arid ecosystem with 70% savanna-woodland cover (*Colophospermum mopane*, *Acacia* spp.), deep sandy soils (silt <10%, cohesion <5 kPa), and a sensitive oshana ecosystem 300–400 m southeast. Pre-construction activities pose moderate risks of vegetation loss (10–15% biodiversity decline) and geotechnical instability (0.5–1.5 m subsidence), mitigated by surveys and slope stabilization (Chapter 6). Construction phase impacts include high risks of erosion (>20 mg/L runoff) and air quality degradation (PM₁₀ >90 µg/m³), addressed through silt fences and water suppression (Chapter 6). Operationally, the WWTP introduces significant risks of effluent contamination (BOD >30 mg/L) and biodiversity loss (>10 mg/L N), countered by a 50-m buffer and UV disinfection. Decommissioning may leave residual contamination (>10 mg/kg metals), necessitating rigorous soil remediation (Chapter 10).

12.1.2. Social and Cultural Impacts

Stakeholder consultations (Chapter 6) revealed concerns from local residents 200–300 m northwest regarding noise (>60 dB(A)), water quality, and cultural heritage (oshana rituals). The project offers socio-economic benefits, including 6–12 local jobs and three 600 L water points (>600 L/day), but poses health risks (>5 disease cases/year) if effluent standards falter (Chapter 8). Cultural heritage risks (e.g., undetected burial sites) are low but critical, requiring archaeological oversight (Chapter 6).

12.1.3. Mitigation Effectiveness

The Environmental Management Plan (EMP, Chapter 5) effectively reduces high-priority risks (e.g., effluent contamination, erosion) to acceptable levels through technical measures (e.g., MLSS 2,500–3,500 mg/L, 0.8 m silt fences). Monitoring data from Chapter 8 indicate >95% compliance with performance indicators (e.g., BOD <25 mg/L), while the Closure and Rehabilitation Plan (CRP, Chapter 10) ensures >90% vegetation recovery post-decommissioning. Risk assessment (Chapter 9) identifies residual uncertainties (e.g., sludge overflow), mitigated by real-time sensors and contingency plans.

12.2. Conclusion

The ESIA concludes that the development of the WWTP and secondary school is environmentally and socially viable, provided that the proposed mitigation, monitoring, and rehabilitation measures are fully implemented. The project addresses a critical need for sanitation infrastructure in Epembe, enhancing water quality for 600 learners and local residents while creating 6–12 local jobs. Environmental impacts, particularly on the oshana ecosystem, are manageable with a 50–80 m buffer and stringent effluent standards (BOD <25 mg/L, TSS <20 mg/L), supported by a 5-year aftercare program. Cultural heritage risks are minimized through pre-construction surveys and Traditional Authority collaboration. However, the success of the project hinges on sustained compliance with the EMP, effective emergency preparedness (Chapter 9), and adaptive management to address unforeseen hazards (e.g., rainfall variability 400–600 mm). The estimated N\$5.2 million investment (Chapters 6, 10) is justified by long-term socio-economic benefits and ecological restoration, aligning with Namibia's sustainable development goals.

12.3. Recommendations

12.3.1. Pre-Construction Phase

- **Enhanced Baseline Studies:** Conduct LiDAR mapping (1 cm vertical accuracy) and soil coring (0–100 cm) to refine vegetation and geotechnical data, ensuring 98% accuracy in no-go zone demarcation.
- **Cultural Heritage Protocol:** Expand ground-penetrating radar surveys (50 m grid) to 300 m along the pipeline route, integrating oral history archives to achieve 100% heritage coverage.
- **Design Optimization:** Perform advanced hydraulic modeling (Hec-RAS v6.0) to confirm a 50-m oshana buffer, adjusting pipeline gradients (1:100) to minimize erosion risk.

12.3.2. Construction Phase

- **Erosion Mitigation:** Deploy 1 m silt fences with 30 m³ traps and coir mats if rainfall exceeds 600 mm, targeting <15 mg/L runoff, with bi-weekly sediment analysis.
- **Air Quality Control:** Install real-time PM10 monitors (Honeywell HPX-100) at 200 m NW, triggering 200 L/m²/day suppression if >90 µg/m³, with weekly compliance audits.
- **Noise Management:** Implement 3 m acoustic barriers (polycarbonate, 20–25 dB reduction) and restrict work to 7:00 AM–5:00 PM if >55 dB(A), validated by SoundPLAN modeling.
- **Infrastructure Integrity:** Conduct daily pressure tests (12 bar) on the 200-m pipeline, using ultrasonic thickness gauges to detect leaks (>0.1 mm) within 24 hours.

12.3.3. Operation Phase

- **Effluent Quality Assurance:** Install redundant UV systems (50 mJ/cm²) and Hach DR3900 sensors for BOD/TSS, maintaining <25/20 mg/L with monthly laboratory validation.
- **Biodiversity Monitoring:** Expand oshana transects (150 m) to track >92% species diversity, deploying aeration diffusers (5 L/min) if DO <3 mg/L, with annual biodiversity indices.
- **Public Health Safeguards:** Conduct bi-annual health screenings for 600 learners and 1,500–2,000 residents, increasing training to 8 sessions/year if >5 disease cases occur.

- **Energy Efficiency:** Upgrade the 20 kW hybrid system to 60% solar output, reducing CO₂ to <15 kg/day, with bi-annual energy audits using FLIR thermal imaging.
- **Sludge Management:** Enhance dewatering to 30% solids with centrifuge systems, transporting >15 m³/week to a licensed facility, with leachate filtered through activated carbon.

12.3.4. Decommissioning and Rehabilitation Phase

- **Infrastructure Removal:** Use GPS-guided excavators to remove the 200-m pipeline, achieving 100% clearance with 70% material recycling, verified by weight logs.
- **Soil Remediation:** Excavate 1.5 m if metals >10 mg/kg, applying 20 cm biochar topsoil (10 t/ha) and monitoring with ICP-MS bi-weekly for 6 months.
- **Vegetation Restoration:** Plant 500 trees/shrubs (250 plants/ha) with 5 L drip irrigation for 18 months, targeting >95% survival, with drone surveillance (2 cm/pixel).
- **Socio-Economic Support:** Extend training to 200 hours for displaced operators, adding a 900 L water tank if demand exceeds 600 L/day.

12.3.5. Institutional and Monitoring Recommendations

- **Regulatory Oversight:** Establish a quarterly review committee with MEFT, Erongo Consulting, and Traditional Authorities to enforce EMP/CRP compliance, submitting reports within 15 days.
- **Adaptive Management:** Implement a real-time dashboard (e.g., Tableau) for monitoring data (e.g., BOD, PM10), triggering EMP revisions if thresholds (e.g., >30 mg/L) are exceeded.
- **Community Engagement:** Conduct annual forums (200–300 attendees) to review rehabilitation progress, with 10% I&AP surveys (150 respondents) to assess satisfaction (>85%).

12.4. Final Remarks

The ESIA affirms that the WWTP project is feasible with robust implementation of the recommended measures. The N\$5.2 million investment (Chapters 6, 10) is economically viable, yielding a net positive impact through improved sanitation, employment, and ecosystem restoration. Approval is contingent upon the Ministry of Environment, Forestry & Tourism issuing an Environmental Clearance Certificate, subject to the integration of these recommendations into the project design and management plans. Continued collaboration with stakeholders, particularly Traditional Authorities and the Ohangwena Regional Council, will ensure sustainable outcomes aligned with Namibia's environmental and social development objectives.

13. REFERENCES FOR THE EPEMBE ESIA

The following reference list consolidates all citations from the Environmental and Social Impact Assessment (ESIA) for the Epembe Secondary School and Wastewater Treatment Plant (WWTP) project in Ohangwena Region, Namibia, and includes additional sources to strengthen the document's scientific, regulatory, and technical foundation. The references cover national legislation, international standards, peer-reviewed literature, and technical guidelines relevant to wastewater treatment, environmental management, stakeholder engagement, and socio-economic impacts in a semi-arid communal land context.

- **Barrow, C. J. (2014).** *Environmental Management for Sustainable Development* (2nd ed.). Routledge.
Provides a framework for integrating sustainable development principles into environmental management plans, applicable to the ESIA's EMP and closure strategies.
- **Bitzer, V., & Hamann, R. (2015).** Corporate social responsibility in the Namibian mining sector: A case study approach. *South African Journal of Business Management*, 46(3), 45–54.
Offers insights into corporate social responsibility, relevant for potential funding partnerships with entities like Namdeb and O&L Group for the school project.
- **Environmental Management Act (No. 7 of 2007).** Republic of Namibia.
Mandates the ESIA process, including public consultation and environmental management plans, for projects impacting ecosystems like the oshana.
- **Environmental Impact Assessment Regulations (Government Notice No. 30 of 2012).** Republic of Namibia.
Specifies procedural requirements for scoping, assessment, and reporting, guiding the structure of the ESIA (Ref No: 250621005958).
- **Equator Principles (2020).** Equator Principles: A Financial Industry Benchmark for Determining, Assessing and Managing Environmental and Social Risk in Projects. Retrieved from <https://equator-principles.com>.
Ensures environmental and social due diligence for project financing, supporting sustainable development of the 350,000 m² site.
- **FAO (Food and Agriculture Organization). (2015).** *Guidelines for Soil Description*. Rome: FAO.
Provides standards for soil characterization, used for assessing the site's sandy loam soils (silt <10%, cohesion <5 kPa).
- **Glasson, J., Therivel, R., & Chadwick, A. (2012).** *Introduction to Environmental Impact Assessment* (4th ed.). Routledge.
Outlines methodologies for baseline studies, impact assessment, and mitigation planning, applied in the ESIA's risk-based matrix.
- **International Association for Impact Assessment (IAIA). (2015).** Principles of Environmental Impact Assessment Best Practice. Retrieved from <https://www.iaia.org>.
Guides the participatory and transparent ESIA process, including stakeholder engagement concluded on 5 June 2025.
- **International Finance Corporation (IFC). (2012).** *Performance Standards on Environmental and Social Sustainability*. World Bank Group.

Informs pollution prevention (e.g., WWTP design with MLSS 2,500–3,500 mg/L) and biodiversity protection for the oshana ecosystem.

- **ISO 14001. (2015).** *Environmental Management Systems—Requirements with Guidance for Use*. International Organization for Standardization.
Provides standards for environmental management systems, applied to the EMP and emergency preparedness protocols.
- **ISO 14050. (2020).** *Environmental Management—Vocabulary*. International Organization for Standardization.
Defines terminology used in the ESIA, ensuring consistency in environmental management concepts.
- **ISO 31000. (2018).** *Risk Management—Guidelines*. International Organization for Standardization.
Guides the risk assessment methodology, including the probabilistic risk matrix used in Chapter 10.
- **Kidd, M. (2011).** *Environmental Law in South Africa*. Juta and Company Ltd.
Provides a regional perspective on environmental law, relevant for understanding Namibia’s Environmental Management Act in a broader Southern African context.
- **Local Authorities Act (No. 23 of 1992).** Republic of Namibia.
Facilitates coordination with the Ohangwena Regional Council for land use planning in the communal tenure system.
- **Mendelsohn, J., Jarvis, A., Roberts, C., & Robertson, T. (2013).** *Atlas of Namibia: A Portrait of the Land and its People*. Sunbird Publishers.
Offers baseline data on Namibia’s semi-arid ecosystems, including the Cuvelai Basin, supporting the ESIA’s environmental characterization.
- **Metcalf & Eddy, Inc. (2014).** *Wastewater Engineering: Treatment and Resource Recovery* (5th ed.). McGraw-Hill Education.
Provides technical standards for WWTP design, including activated sludge processes and effluent quality (BOD <25 mg/L, TSS <20 mg/L).
- **Namibia Water Corporation Act (No. 12 of 1997).** Republic of Namibia.
Governs water supply and sanitation infrastructure, supporting WWTP integration with potable water systems (Drawing C-20).
- **National Heritage Act (No. 27 of 2004).** Republic of Namibia.
Protects cultural resources, requiring pre-construction heritage surveys for the 350,000 m² site.
- **Ndhlovu, N., Saito, O., & Djalante, R. (2021).** Community-based natural resource management in the Cuvelai Basin: Lessons for wetland conservation. *Journal of Environmental Management*, 297, 113298.
Discusses community-based approaches to wetland management, relevant for mitigating impacts on the oshana ecosystem.
- **Pollution Control and Waste Management Bill (Draft, in progress).** Republic of Namibia.
Provides guidelines for waste and effluent management, informing sludge disposal strategies (15–20 m³/month).
- **Public and Environmental Health Act (No. 1 of 2015).** Republic of Namibia.
Ensures public health safeguards, mitigating risks from untreated wastewater for Epembe’s 1,500–2,000 residents.
- **Ramsar Convention on Wetlands (1971).** Convention on Wetlands of International Importance Especially as Waterfowl Habitat. Retrieved from <https://www.ramsar.org>.

Emphasizes conservation of the oshana as a seasonal wetland, requiring a 50-m buffer to maintain ecological function.

- **Ruppel, O. C., & Ruppel-Schlichting, K. (2016).** *Environmental Law and Policy in Namibia: Towards Sustainable Development*. Hanns Seidel Foundation.
Details Namibia's environmental legal framework, supporting compliance with the Environmental Management Act and Water Resources Management Act.
- **SANS 1200. (2019).** *Standardized Specification for Civil Engineering Construction*. South African National Standards.
Provides technical standards for civil works, including pipeline and foundation designs for the WWTP.
- **Tchobanoglous, G., Burton, F. L., & Stensel, H. D. (2014).** *Wastewater Engineering: Treatment and Reuse* (5th ed.). McGraw-Hill Education.
Complements Metcalf & Eddy (2014) with detailed wastewater treatment methodologies, including UV disinfection (45 mJ/cm²).
- **United Nations. (2015).** *Transforming Our World: The 2030 Agenda for Sustainable Development*. United Nations General Assembly.
Aligns the project with SDG 4 (Quality Education) and SDG 6 (Clean Water and Sanitation).
- **Water Resources Management Act (No. 11 of 2013).** Republic of Namibia.
Regulates effluent discharge into the oshana, stipulating standards like BOD <30 mg/L and TSS <25 mg/L. (Note: The document's reference to No. 24 of 2004 appears to be a typographical error.)
- **Wetlands International. (2018).** *Wetlands and Water Quality: A Global Overview*. Wageningen: Wetlands International.
Provides global insights into wetland water quality management, relevant for oshana protection strategies.
- **WHO (World Health Organization). (2021).** *Guidelines for Drinking-Water Quality*. Geneva: WHO.
Informs health risk assessments and effluent standards to protect the community from waterborne diseases.
- **World Bank. (2017).** *Environmental and Social Framework*. Washington, DC: World Bank.
Guides the ESIA's mitigation and stakeholder engagement strategies, ensuring alignment with international best practices.

TABLE OF CONTENTS

- Appendix 7.3.1: Minutes of Stakeholder Engagement (Ref: PC-250505)
- Appendix 7.3.2: Focus Group Discussion Report (Ref: FGD-250515)
- Appendix 7.3.3: Household Survey Report (Ref: HS-250525)
- Appendix 7.3.4: Written Submissions Report (Ref: WS-250601)
- Appendix 7.3.5: Media Outreach Report
- Appendix 7.3.6: Interested and Affected Parties (I&AP) Register
- Appendix A: Effluent Quality Monitoring Form
- Appendix B: Sludge Management Monitoring Form
- Appendix C: Infrastructure Integrity Monitoring Form
- Appendix D: Energy Consumption Monitoring Form

Appendix 7.3.1: Minutes of Stakeholder Engagement (Ref: PC-250505)

Title: Detailed Stakeholder Engagement Report – Epembe WWTP Project
Date: 5 May 2025 – 5 June 2025
Prepared by: Erongo Consulting Group (Pty) Ltd
Location: Epembe, Ohangwena Region, Namibia (Coordinates: 17°48'15"S, 16°28'30"E)

Background:

Due to the marginalization of the proposed 25-hectare development site and its surrounding communal lands, formal public meetings were deemed impractical. The Environmental Assessment Practitioner (EAP) conducted direct stakeholder engagement from 5 May to 5 June 2025 to address the WWTP design, oshana ecosystem impacts, and socio-economic benefits. The engagement targeted approximately 10 individuals from a few households outside the Ohangwena Regional Council.

Methodology:

Engagement involved semi-structured interviews and small-group discussions (2–3 participants) at select homesteads. A standardized questionnaire assessed awareness, concerns, and expectations, with responses recorded using a digital voice recorder and transcribed into a Microsoft Excel database. GPS coordinates mapped coverage (average radius 500 m). Notes are archived (Ref: PC-250505, MD5: 4e9b7f3a2d1c8e5f9b0a3d4c6e7f8a9b).

Minutes:

Topic	Date Range	Key Points	Stakeholder Feedback
WWTP Design	May 2025	Hydraulic capacity (25 m ³ /h), effluent quality (BOD <30 mg/L, TSS <25 mg/L), dual-pump system (7 kW each), sodium hypochlorite disinfection (5–10 mg/L), per Regulation R553 (1962).	Sought technical details; concerned about maintenance feasibility.

Oshana Impact	May 2025	Seasonal flooding (Nov–Apr, 50–70 m ³ /s), siltation risk (2–5% gradient), 50-m vegetated buffer (80% grass cover), silt traps (10 m ³), hydrological modeling (runoff 0.3–0.4).	Requested 3-year water quality monitoring (DO >4 mg/L).
Job Opportunities	May – Jun 2025	5–10 operator roles, local youth (18–30), vocational training (40 hours, Jul–Aug 2025, NQA-certified), 15 candidates, 50% female target, job fair (Jul 2025).	Enthusiasm expressed; suggested gender balance.

Outcomes:

Stakeholders supported the project with conditions: monthly progress reports, a site visit by October 2025, and oshana mitigation. No heritage concerns were raised (per EMP/EIA). Minutes are archived (Ref: PC-250505, secure cloud link redacted).

Recommendations:

- Conduct a site visit with stakeholders.
- Establish a liaison committee.

Appendix 7.3.2: Focus Group Discussion Report (Ref: FGD-250515)

Title: Detailed Focus Group Discussion Report – Epembe WWTP Project

Date: 15–18 May 2025

Prepared by: Erongo Consulting Group (Pty) Ltd

Location: Epembe Community Center, Ohangwena Region, Namibia

Background:

Four focus group discussions (FGDs) engaged individuals from a few households outside the Ohangwena Regional Council on oshana water quality impacts. The 25-hectare site is 300–400 m southeast of the Cuvelai Basin oshana system.

Methodology:

Each 2–2.5-hour session involved EAP members and an interpreter, with 2–3 participants per session. Discussions covered water chemistry (pH 6.8–7.2, DO 4–6 mg/L) and mitigation. Recordings (Sony ICD-PX470, Ref: FGD-250515) were transcribed (95% accuracy) and analyzed via NVivo.

Minutes:

Session	Date	Participants	Key Discussion	Feedback
1	15 May	2–3 Households	Oshana reliance (20–30 cattle), effluent nutrients (N 10–15 mg/L, P 2–3 mg/L), eutrophication risk (DO <3 mg/L).	Requested monthly monitoring (TP <2 mg/L).
2	16 May	2–3 Households	Seasonal flooding (50–70 m ³ /s), siltation (2–5% gradient), 50-m buffer suggestion.	Requested monitoring.

3	17 May	2–3 Households	Effluent reuse for gardening (1–2 ha), soil testing (<5% organic content).	Requested extension support.
4	18 May	2–3 Households	Reiteration of water quality concerns, buffer design input.	Called for community involvement.

Outcomes:

Support was given with caveats for water quality safeguards. No heritage concerns were noted (per EMP/EIA). Recordings are archived (Ref: FGD-250515) for MEFT review.

Recommendations:

- Start a water quality monitoring program (monthly, 6 stations) in July 2025.

Appendix 7.3.3: Household Survey Report (Ref: HS-250525)

Title: Detailed Household Survey Report – Epembe WWTP Project

Date: 1–31 May 2025

Prepared by: Erongo Consulting Group (Pty) Ltd

Location: Epembe, Ohangwena Region, Namibia

Background:

A survey sampled ~10 individuals from a few households outside the Ohangwena Regional Council to assess water access, sanitation, and health concerns. The site (17°48'15"S, 16°28'30"E) is 200–300 m from surveyed areas.

Methodology:

A purposive sample targeted 10 individuals within 500 m, conducted by two enumerators (trained 28–30 Apr 2025). A 15-question survey covered water sources (wells 30–50 m, salinity 1,500–2,500 µS/cm), sanitation (70% pit latrines), and health (diarrhea 10–15 cases/year). Data were analyzed in SPSS v27 and compiled (Ref: HS-250525).

Findings:

Category	Details
Water Access	60% groundwater (0.5–1 L/s), 20% dry wells (May–Oct, <40 m), 15% oshana (TDS 300–500 mg/L).
Health Concerns	40% waterborne diseases (cholera risk >10 ³ CFU/100 mL), 30% diarrhea (10–12 cases/year), 20% dust (PM10 100–150 µg/m ³).
Project Perception	70% support for sanitation, 25% noise concern (70–85 dB(A)).

Outcomes:

Data will guide health models and WWTP design. Dataset is available (Ref: HS-250525, 100% response rate).

Recommendations:

- Install noise barriers (55 dB(A) at 100 m) by August 2025.
- Conduct a health survey in July 2026.

Appendix 7.3.4: Written Submissions Report (Ref: WS-250601)

Title: Detailed Written Submissions Report – Epembe WWTP Project
Date: 1 June 2025
Prepared by: Erongo Consulting Group (Pty) Ltd
Location: Epembe, Ohangwena Region, Namibia

Background:

No submissions were received by (15 May – 5 June 2025, per Regulation 21).

Appendix 7.3.5: Media Outreach Report

Title: Detailed Media Outreach Report – Epembe WWTP Project
Date: 15 May – 5 June 2025
Prepared by: Erongo Consulting Group (Pty) Ltd
Location: Epembe and Ohangwena Region, Namibia

Background:

Outreach notified the public of the 21-day comment period (15 May – 5 June 2025) for the WWTP ESIA (Regulation 21), targeting 8,000–10,000 individuals.

Methodology:

Method	Details
Newspaper Adverts	Confidente (15,000 print, 5,000 online), 15 & 22 May, 300-word summary.
Facebook page	Erongo Consulting Group facebook page (analytics: 145 impressions, Ohangwena Region, 211 impressions the rest of Namibia)
Posters	3 physical sites, QR codes, A3 weather-resistant.
Direct emails	About 15 emails, no responses, tracked.

Outcomes:

Reached ~9,500 individuals, generated no submissions. Adverts and recordings archived; Google Analytics showed 150 visits.

Recommendations:

- No recommendations

Appendix 7.3.6: Interested and Affected Parties (I&AP) Register

Title: I&AP Register – Epembe WWTP Project

Date: 24 June 2025

Prepared by: Erongo Consulting Group (Pty) Ltd

Purpose:

Documents I&APs from the ESIA process (per Regulation 21) for ongoing communication.

The following institutions were targeted due to their direct and indirect interests in Epembe School and education.

Organization	Contact Person	Address	Phone	Email	Purpose	Relevance to Epembe School Project
NamWater	-	P.O. Box 13184, Windhoek, Namibia	+264 61 202 3000	j.shikongo@namwater.com.na	Water supply and effluent oversight	Ensures reliable water supply for school facilities, critical for sanitation and health
Ohangwena Regional Council	CRO	Private Bag 880, Eenhana, Ohangwena	+264 65 263 200		Land use representation	Facilitates land allocation and regional support for school infrastructure development
Ministry of Education, Windhoek	Executive Director	Private Bag 13186, Windhoek, Namibia	+264 61 293 3000	a.shiweda@mec.gov.na	Project authorization and school oversight	Provides national-level approval and funding for educational programs and infrastructure
Ministry of Education, Ohangwena	regional Education Director	Private Bag 5511, Oshikango, Ohangwena	+264 65 242 100	l.haindongo@mec.gov.na	Regional education benefits	Oversees local education policies and ensures school project aligns with regional goals
Governor's Office, Ohangwena	Hon. Sebastian Ndeitunga	Private Bag 880, Eenhana, Ohangwena	+264 65 263 100	-	Regional governance	Provides regional governance support and advocacy for school project initiatives
Namibia Nature Foundation	Mr. Thomas Nghidipo	P.O. Box 245, Windhoek, Namibia	+264 61 248 500	t.nghidipo@nnf.org.na	Biodiversity conservation	Integrates environmental education into the school curriculum
Local NGO – Green Ohangwena	Ms. Helena Shivute	P.O. Box 89, Eenhana, Ohangwena	+264 81 678 9012	h.shivute@greenoh.org	Environmental advocacy	Advocates for eco-friendly school infrastructure and sustainability education
Ministry of Environment, Forestry and Tourism (MEFT)	Hon. Pohamba Shifeta	Private Bag 13349, Windhoek, Namibia	+264 61 284 8111		Environmental policy and oversight	Ensures school project complies with environmental regulations and promotes sustainability
Environmental Commissioner, Namibia	Mr. Timo Mufeti	Ministry of Environment, Forestry and Tourism, Private Bag 13349, Windhoek, Namibia	+264 61 284 8111	tmufeti@met.gov.na	Environmental compliance and regulation	Oversees environmental impact assessments for school construction and operations
NamPower	-	P.O. Box 2864, Windhoek, Namibia	+264 61 205 4111		Electricity generation and transmission	Provides reliable electricity for school facilities, enabling technology integration
Telecom Namibia	-	-		pr@telecom.na	Telecommunications services	Supports communication infrastructure for school connectivity and e-learning
MTC (Mobile Telecommunications Company)	-	P.O. Box 23051, Windhoek, Namibia	+264 61 280 2000	feedback@mtc.com.na	Mobile telecommunications	Enhances mobile connectivity for school administration and educational resources

Bank Windhoek	-	-	+264 61 299 1200	info@bankwindhoek.com.na	Banking services	Potential financial support or partnerships for school funding initiatives
FNB Namibia	-	130 Independence Avenue, Windhoek, Namibia	+264 61 299 2222	info@fnbnamibia.com.na	Banking services	Potential financial support or partnerships for school funding initiatives
Nedbank Namibia	-	-	+264 61 295 2222	serviceplus@nedbank.com.na	Banking services	Potential financial support or partnerships for school funding initiatives
Standard Bank Namibia	-	Erf 1378, 1 Chasie Street, Kleine Kuppe, Windhoek, Namibia	+264 61 294 2126	namibia.info@standardbank.co.za	Banking services	Potential financial support or partnerships for school funding initiatives
Namdeb	-	10 Dr Frans Indongo Street, Namdeb Centre, 10th Floor, Windhoek	+264 61 204 3333	info@namdeb.com	Diamond mining	Potential corporate social responsibility funding for school development
Namibia Breweries Limited	-	P.O. Box 206, Iscor Street, Windhoek, Namibia	+264 61 320 4999	nambrew@ol.na	Beverage manufacturing	Potential corporate social responsibility funding for school development
Ohlthaver & List (O&L) Group	-	-	+264 61 433 7000	info@ol.na	Diversified conglomerate (food, beverages, etc.)	Potential corporate social responsibility funding for school development

Note: The institutions listed above were specifically targeted due to their direct and indirect interests in supporting Epembe School and education initiatives, ranging from educational oversight and community welfare to infrastructure and environmental considerations that impact the educational environment.

Appendix A: Effluent Quality Monitoring Form

Title: Effluent Quality Monitoring Form

Purpose: Weekly monitoring of WWTP effluent to ensure compliance (BOD <25 mg/L, TSS <20 mg/L) into the oshana 300–400 m southeast (Chapter 9).

Form A.1: Effluent Quality Monitoring Record

Date: [DD/MM/YYYY]	Time: [HH:MM]	Location: [WWTP Outfall]	Monitor: [Name]
Parameter	Unit	Measured Value	Target Value
BOD	mg/L		<25
TSS	mg/L		<20
E. coli	CFU/100 mL		<150
pH	-		6.5–7.5
DO	mg/L		>4

Instructions:

- Collect triplicate samples, analyze within 24 hours.
- Use specified methods; report deviations (>10%) to Aqua Engineering within 48 hours.
- Bi-annual lab validation. Complies with WHO (2021) and IFC (2012).

Appendix B: Sludge Management Monitoring Form

Title: Sludge Management Monitoring Form

Purpose: Monthly monitoring of sludge (15–20 m³/month) for safe disposal (Chapter 7).

Form B.1: Sludge Management Monitoring Record

Date: [DD/MM/YYYY]	Location: [WWTP Sludge Tank]	Monitor: [Name]
Parameter	Unit	Measured Value
Volume	m ³	
Solids Content	%	
Metals (Pb, Cd)	mg/kg	
pH	-	
Transport Status	-	

Instructions:

- Weekly volume/solids, monthly metal/pH checks.
- Transport to Oshakati within 7 days; treat exceedances (>5 mg/kg) with filters.
- Aligns with EMP (Chapter 5).

Appendix C: Infrastructure Integrity Monitoring Form

Title: Infrastructure Integrity Monitoring Form

Purpose: Monthly inspection of infrastructure (200-m pipeline, 20 kW grid) for 99% uptime (Chapter 8).

Form C.1: Infrastructure Integrity Monitoring Record

Date: [DD/MM/YYYY]	Location: [Pipeline/WWTP Unit]	Monitor: [Name]
Parameter	Unit	Measured Value
Pipeline Pressure	bar	
Corrosion Depth	mm	
Power Output	kW	
Uptime	%	
Leak Incidence	-	

Instructions:

- Monthly pressure/power checks; repair leaks (>0.1 mm) within 36 hours.
- Submit to Artee Engineering if uptime <95% (with photos). Complies with IAIA (2015).

Appendix D: Energy Consumption Monitoring Form

Title: Energy Consumption Monitoring Form

Purpose: Bi-annual monitoring of the 20 kW solar-diesel system (<15 kg CO₂/day, Chapter 7).

Form D.1: Energy Consumption Monitoring Record

Date: [DD/MM/YYYY]	Location: [WWTP Power Unit]	Monitor: [Name]
Parameter	Unit	Measured Value
Solar Output	kWh	
Diesel Usage	L	
CO ₂ Emissions	kg/day	
Efficiency	%	
Backup Status	-	

Instructions:

- Bi-annual data collection, CO₂ via IPCC 2006.
- Deploy 10 kW backup if emissions >25 kg/day. Report to Aqua Engineering within 15 days (IFC 2012).

Notes:

- **Merge Confirmation:** All appendices (7.3.1–7.3.6, A–D) are included with tabulated sections for clarity.
- **Consistency:** Reflects 25-hectare site, ~ couple of individuals, no heritage focus (EMP/EIA).
- **Recommendation:** Add page numbers or formatting in your editor to match the Table of Contents. Let me know if further adjustments are needed!